Revision		Date	By
A	Recalculated due to change in door measurements	2019-02-12	EB

LOAD DIAGRAM

Nominal static vertical loads are indicated. Value within brackets include dynamic surload factor 1.25 for door leaf loads in open position. Includes items provided by ASSA ABLOY only.


DISTRIBUTED LOAD: 24.5kN
1.5kN
0.3kN
6.4kN
DISTRIBUTED LOAD: 24.5kN
1.5kN
1
1
1
1
Door #1
Mullion #12
Door #2

Interior view, Door closed


8.0kN
(10.0kN)
DISTRIBUTED LOAD: 8.5kN
1.5kN
6kN
if arresting
2.4kN
(3.0kN)
4.3kN
8.0kN
(10.0kN)
8.0kN
(10.0kN)
DISTRIBUTED LOAD: 8.5kN
1.5kN
8.0kN
(10.0kN)
Pre-installation test load:31.6kN
(Mullion vertical, doors open)
Door #1
Mullion #12
Door #2

Interior view, Door open


Differential pressure transferred from mullion to door head steel: 12kN
Differential pressure transferred from mullion to wind brace bracket: 69kN
Differential pressure transferred from door leaves to mullion base guide: 27kN


F= 1.5kN
300
℄ Door

Section @ gear motor
SK 973.1Z-100LA/4
Scale 1:20


Guide rail
Door jamb
F
98
TW

Force by differential pressure
transferred to guide rail at
each intermediate position.
(located at pos 1)
F= 7.5kN


F=1.9kN
F=1.9kN
℄ Door leaf

Load on header box attachment
(each screw), due to wind load
and door weight



Working load: 5kN
Rupture load: 35kN
Chain hoist rotation during lifting sequence. Scale 1:20



Arresting load: 6.5kN

Extra load arrester rotation during lifting sequence. Scale 1:20

Steel building company in cooperation with door installing company must make a pre-installation load test on the structure, where the mullions are located, in order to simulate the vertical deflection of the structure that occurs when doors are installed. This vertical deflection figure will be used to determine the correct installation level of the mullions. Required material/equipment and personnel by others than ASSA ABLOY

NOT INCLUDED IN DOOR SUPPLY:
1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Design and supply of coverage, such as roofing or enclosure, for door components at door head.
4. Door jambs adjustable for overall door width and true to plumb.
5. Paint job after completed door installation.
6. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:
7. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
8. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
9. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
10. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
11. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
12. Header box must be accessible from both sides during installation.

DOOR PROPERTIES:
13. The door is designed to withstand a differential pressure of 1.0kPa.
13. Mullion and mullion pit are designed to allow for 0mm of downward deflection and 0mm of upward deflection due to external loads such as wind.
14. Guide rails, top- and intermediate beams in extruded aluminium with natural finish.
15. Environmental category: Megadoor standard
16. Bottom beam in carbon steel painted: Light grey (RAL7047)
17. Colored clamp strips on both sides.
18. Door header box enclosed on motor sides.
19. Color of header box: BLACK (NCS 9000-N. RAL 9005)
20. The door fabric is a UV stabilized, flame retardant, self-extinguishing, PVC coated polyester fabric with fire technical properties Euroclass C-s2, d0 (according to EN 13501-1:2007).
Colour of fabric: TRANSLUCENT WHITE

ELECTRICAL:
21. One main control panel provided of PLC type.
22. Control mode : Impulse up / Constant contact down.
23. Cables are included.
24. Back-up power socket & switch.
25. Audible & visual alarm.
26. Approx. size of main control panel: WxHxD (500x600x250mm),
27. Location of main control panel: TBC.
28. Aux. Voltage 24VDC
29. Power supply: 400V /3Ph /50Hz
30. Power: 7.7kW
31. Nom. current: 16.A
32. Start current: . 82.4A
33. (max. allowed voltage drop at start: 5%)

BELT HOIST UNITS Doors #1&2:
SK 973.1Z-100M/4
75mm wide polyester belt. Rupture load 80kN/belt.

MULLION CHAIN HOISTS:
DEMAG DC-PRO2.
Chain rupture load: 22kN

EXTRA LOAD ARRESTER
SALA PL-A 400-8

DOOR IDENTITY NUMBER: 84384001

INTERFACE DRAWING, ref. to drwng. no. 68127

DESIGNED EB
SIZE A1F
SCALE 1:75
CODE 84384
ITEM NO
DATE 2019-02-05
ASSA ABLOY
If not otherwise stated:
Tolerances
ISO 2768-m
EN ISO 13920-B
Cutting class
ISO 9013-442
Weld class
ISO 5817-C
Surface finish
Smooth raw surface

NVIDIA Phase 2
India
Megadoor 37450 x 3609/2959
Load diagram & Notes

PLOT DATE
DRAWING NO 68128
REVISION A

This document is the property of ASSA ABLOY Entrance Systems AB and shall not without our written permission be copied, imparted to a third party or used for any other unauthorized purpose.