NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Adani Wilmar Limited
Adani Wilmar Limited Bundi
Kota Jaipur hi way silore Road , Bundi

Project, Location : Bundi, Rajasthan

Date : 24.11.2020
Quote NO : SQT.20.21.2846
Kind Attn : Imran Ali
Email Id : Imran.Ali@Adaniwilmar.In
Contact No: 7665006863

Subject : Quotation for Motorized Single Leaf Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Single Leaf Sliding Gate**	8500	2200	1	400,000	400,000	20,000	20,000
2	**Manual Wicket Gate**	2000	2200	1	57,000	57,000	10,000	10,000
	Total			**1**		**457,000**		**30,000**
3	P&F Charges			3%		13,710		
	Total Without Taxes					470,710		30,000
	GST Extra @ 18%			18%		84,727.80		5,400
	Total With Taxes					**555,438**		**35,400**
4	Transportation Charges					Extra at atcual		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Single Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	**Door type**	Motorized Single Leaf Sliding Gate
2	**Opening Direction**	Horizontal - from left to right or reverse
3	**Mounting Location area**	Inside area
4	**Design Pattern**	Standard Tubular Design Pattern
5	**Outer Tube**	80 x 80 x 3.6 mm THK SQ. TUBE
6	**For Post**	80 x 80 x 3.6 mm THK SQ. TUBE
7	**Innear Tube**	32 x 32 x 2.6 mm THK SQ. TUBE
8	**Gap Between Tubes**	125mm
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Guide Rollers supporter during Gate**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of
12	**Painting**	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	**El motor make**	BFT – Italy (100% imported)
14	**Emergency Operation**	Manual after turn the switch
15	**Operating Switch**	Push Button from inside
16	**Safety**	Photocells, Flashing Light

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Amol Gaware on 7758820333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd