NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No. SQT/19-20/2517 **Date : 26.03.2020**

Aditya Construction
Pune

Kind Attn : Mr. Ashok
Email : adityaconstructionpune@gmail.com
Contact No : 9011042905

Project Name And Location :

Subject : Revised Quotation for Motorised Rolling Shutter & Sliding gate.

Dear Sir

Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No	Description	Qty Sq m	Unit	Rate / Sq M in INR	Net Amount INR
A	**Motorized Rolling Shutter** **MS Slat:1mm (Width less than 3.5M) and 1.2mm (Width more than 3.5M)Thk, Curved Type Profile with heavy duty Shaft, Guide, Indirect Drive Motor, Hood Cover with Painting** **(Supply + Installation)**				
1	Size : (W) 4000 mm X (H) 4000 mm	1	Nos.	1,47,000	1,47,000
2	Size : (W) 3000 mm X (H) 3000 mm	1	Nos.	1,06,000	1,06,000
B	**Single Leaf Motorized Sliding Gate** **• Outer Tube - 80 x 80 x 3.2mm MS SQ. TUBE** **• Inner Tube - 40 x 40 x 2mm MS SQ. TUBE** **• Gap - 125 mm** **(Supply + Installation)**				
1	Size : (W) 8000 mm X (H) 1800 mm	1	Nos.	13,44,000	13,44,000

GST Pune		27AAECN0437H1ZM

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% of total supply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST extra @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain** on **08551092333** For any further Clarification /Information in this Concern.

With Best Regards

Varsha

7219207333

For NIHVA Technologies Pvt Ltd