NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0021 **Date : 21-06-2017**

GreyOrange India (P) Ltd
Second Floor, Orient Bestech Business Tower
NH8, Block A, Sector 34,
Gurgaon - 122004, Haryana

Kind Attn : Mr.Kuldeep Singh
Email : kuldeep.s@greyorange.sg
Contact No : 9717791309

Subject : Quotation for Telescopic Conveyor

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
A.Telescopic Conveyor(Make- NIHVA)					
Specifications	**1.Total Length: 12 mtr** **2.Extended Length: 7 mtr** **3.Retracted Size: 5 mtr** **4.No. of Stages: 3** **5.Belt Movement: Bi-directional** **6.Loading Capacity: 75 kg/meter** **7.Material to be handle: Boxes/Bags** **8.Temperature: Ambient** **9.Main Body Of Conveyor: Manufacturing from Ms Plate, Tube Frame Structure** **10.Panel:The conveyor comes with a fixed main panel on rear side and front side only operating panel with emergency .stopper sensor bar , LED lighting , totally consoled wiring.** **11.Speed: 30 mtr per minute with VFD.**	**4**	**Nos**	**2050000**	**82,00,000.00**
B	**Installation Charges For Above**			**150000**	**1,50,000.00**

VAT TIN :	27545250455 V
CST TIN :	27545250455 C
Service Tax No:	AAECN0437HSD001
GST ID:	27AAECN0437H1ZM

Amount in Words	**Total Amount(A+B)**	**83,50,000.00**
	Rupees Eighty Three Lacs Fifty Thousands Only	

Image Attached For your Reference:-



General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3% Extra
3	**Freight Notes**	:	Extra at Actual.
4	**Delivery**	:	9-10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	**80% advance along with confirm Purchase Order & balance before dispatch**
6	**Insurance**	:	Extra if applicable
7	**Sales Tax**	:	Extra as applicable at the time of dispatch. Presently @13.5% VAT (supply within Maharshtra OR @2% CST against Form C (Outside Maharashtra).
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Note : The implementation of "IGST Act and CGST Act along with SGST Act and UTGST ACT " will be enforced as per notified date, accordingly IGST and CGST along with SGST and UTGST will be applicable at prescribed rates and accordingly these taxes will be charged extra

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre

7709586333

For Nihva Technologies Pvt Ltd