
DISTRIBUTED LOAD
Door closed: 11.6kN
Door open: 5.2 kN
Open: 3.2 kN
Closed: 0 kN
Open: 3.2 kN
Closed: 0 kN
A
A
B
B
Control panel
Aprox. 1500
Supply limit
Total height 6475±10
800
1529
Supply limit
(120)
(120)
Clear width 8760
Total width 9000±10
Supply limit
Supply limit

Interior view, Door closed


A
520
Clear height 4988
A slight outward slope
is recommended


Total width
0
177
1207
1907
2453
3000
4000
5000
6000
6547
7093
7793
8823
24x Hole pattern for attachment
at back of header box.
C

SECTION A-A


Clear width 8760
B
Total width 9000±10

SECTION B-B

Door leaf is not shown for clarification


Total width
Nom. 7
0
177

DETAIL C, SCALE (1:10)


Building
Anchor bolt M10 x 112.
55
Door side jamb.
Guide rail
℄ Door
260
79
Clear width
Total width
96

DETAIL B, SCALE (1:10)


Concrete.
To be designed, provided and
installed by others than ASSA ABLOY.
Anchor bolt M10 x 112.
c/c attachment
holes 380
45
45

DETAIL A, SCALE (1:10)

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.

DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.15kPa.
13. Color of door fabric: Please specify
14. Side profiles
15. Metal trim: motor side

ELECTRICAL:

16. One main control panel provided of PLC type.
17. Audible and visual alarm
18. Back-up power switch
19. Safety edge
20. Approx. size of main control panel: WxHxD (500mm x 600mmx250 mm),
21. Power: 2.7kW
22. Nom. current: 6.4A
23. (max. allowed voltage drop at start: 5%)

BELT HOIST UNITS:

SK 873.1-100L/4 Z dual brake


Guide rail
Door jamb
Intermediate beam guide
F
110
Total width

Force by differential pressure
transferred to guide rail at
each intermediate position.
F=4.7 kN


F=1kN
F=1kN
℄ Door leaf

Load on header box attachment
(each screw), due to wind load
and door weight

Building: ARFF5

DESIGNED
KMÖ
SIZE
A1
SCALE
1:50
CODE
22240-22241
ITEM NO
DATE
2021-07-22
ASSA ABLOY
If not otherwise stated:
Tolerances
ISO 2768-m
EN ISO 13920-B
Cutting class
ISO 9013-442
Weld class
ISO 5817-C
Surface finish
Smooth raw surface

Delhi Fire Station
India
Megadoor 8760 x 4988
Sales interface

PLOT DATE
DRAWING NO
74414
REVISION
--

This document is the property of ASSA ABLOY Entrance Systems AB
and shall not without our written permission be copied, imparted to a
third party or used for any other unauthorized purpose.