NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

BR POWER CONTROL & AUTOMATION SERVICES
Plot No.15, Krishana Industrial Area, Gali No 5, Sector 25,
Faridabad(Haryana) 121004 India

Date : 08.05.2021
Quote NO : **MHE_21.22.0006R**
Kind Attn : Mr. Rajesh Sharma
Email Id : brpowercontrol@yahoo.com
Contact No: 9811323296

Project Name & Location: Telescopic Truck Loader/Unloader Conveyor, Faridabad

Subject : Quotation for Telescopic Truck Loader/Unloader Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Truck Loader/Unloader Conveyor**	**2**	**11,25,000**	**22,50,000**	**35,000**	**70,000**
		Total		**22,50,000**		**70,000**
	P&F Charges	3%		**67,500**		
	Total Without Taxes			**23,17,500**		**70,000**
	GST Extra @ 18%	18%		**4,17,150**		**12,600**
	Total With Taxes			**27,34,650**		**82,600**
2	Transportation Charges					**Extra At Actual**
3	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Bags OR Cartons Boxes
2	Maximum Product Size (L x W x H)	600 X 500 X 400 mm
3	Maximum Weight	50 Kg
4	Material Handling Rate	Upto 3000 bags or boxes Per Hour
5	Base Section Length(Retractable)	4000 mm
6	Extension	6000 mm
7	Total Length	10,000 mm
8	No. of Extension Stages	3
9	Basic Overall Height	900 mm
10	Belt Width	600 mm
11	Belt Type	PVC 70 Sh.A/Smooth/Black/LF/Ldb Fabric/2 Ply/3.00 mm/SS/Fastener
12	Belt Speed	25 - 45 mtr/min Variable through VFD, connecting to existing TLX
13	Belt Direction	Bi-directional for loading and unloading
14	Belt Drive	As per Design
15	Telescopi Movement Drive	As per Design
16	Power Supply	240 VAC, 50 Hz
17	Load Capacity	50 Kg/mtr
18	Finish	RAL 5002 ultramarine blue or as per client's request Base coat of Zinc Chromate Primer 2 coats of finish paint
19	Structure Construction	MS Heavy Duty Plates
20	Conveyor Mounting	Adjustable Levelling Mounts with grouting holes
21	Hydralic Lift	Upto 2500 mm from ground level

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd