NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

DESAI CONSTRUCTION PVT. LTD.
Opp. New GIDC, N. H. No. 48,
Gundlav - 396 035, Dist: Valsad, Gujarat.

Date : 16.12.2019
Quote NO : SQT.19.20.2275R2
Kind Attn : Mr. Yogesh Rohit
Email Id : yogesh.rohit@desaiconstruction.com
Contact No: 9376710357

Project Name & Location: GE, Gandhidham

Subject : Revised Quotation for Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorised Single Leaf Sliding Gate	9000	1800	2	276,500	553,000	14,000	28,000
2	Wicket Gate	1470	1800	2	22,500	45,000	7,000	14,000
3	Motorised Cantilever Gate	5000	1800	2	315,000	630,000	15,000	30,000
				Total Value		**1,228,000**		**72,000**
				P&F Charges	NIL	-		
				Total Without Taxes		**1,228,000**		**72,000**
				GST Extra @ 18%	18%	221,040		12,960
				Total With Taxes		**1,449,040**		**84,960**
				Total With Taxes (Supply + Installation)		**1,534,000**		
4	Transportation Charges					**In NIHVA Scope**		
5	Unloading Charges @ Site					**In NIHVA Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications

Motorised Single Leaf sliding Gate

Sr. No	Description	Specifications
1	Door type	Motorised Sliding Gate
2	Clear Opening gate dimension	(W) 9000 mm X (H) 1800 mm
3	Opening Direction	Horizontal - from left to right or reverse
4	Mounting Location area	Inside area
5	Design Pattern	Standard Tubular Design Pattern
6	Outer Frame Tube Sizes	100 x 50 x 3.6 mm
7	Internal Vertical Tube Sizes	25 x 25 x 2.5 mm
8	Gap Between Tubes	75 mm C/C
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
13	Safety	Flashing Light, Safety Photocell
14	Motor	100% Imported from Europe

Motorised Single Leaf Cantilever Gate

Sr. No	Description	Specifications
1	Door type	Motorised Single Leaf Cantilever Gate
2	Clear Opening gate dimension	(W) 5000 X (H) 1800
3	Opening Direction	Horizontal - from left to right or reverse
4	Mounting Location area	Inside area
5	Design Pattern	Standard Tubular Design Pattern
6	Outer Frame Tube Sizes	100 x 50 x 3.6 mm
7	INNEAR TUBE	25 x 25 x 2.5 mm
8	Gap Between Tubes	125mm
9	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
10	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
11	Operation	By Cantilever Mechanism
12	Operating Switch	Push Button from inside
13	Safety	Photocells, Flashing Light
14	Motor	100% Imported from Europe

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope
8	Lifting Equipements	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 18 months from the date of Installation.(Subject to date of installation within one month from date of supply)

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Bhavin Jain on 8551092333**

With Best Regards
Vivek
8350570333
For NIHVA Technologies Pvt Ltd