NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

PUERTO LIFE SCIENCES PRIVATE LIMITED
Plot no. 78 Patparganj Industrial Area
Delhi – 110092.

Date : 09.09.2019
Quote NO : SQT.19.20.1995R
Kind Attn : Mr. PANKAJ BHUJBAL
Email Id : pankajbhujbal@puerto.in
Contact No: 8512835966

Project Name & Location: Delhi

Subject : Quotation for Motorized Sliding gate, Wicket Gate, Boom Barrier

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorised Telescopic Leaf Sliding Gate (With Angle)**	4650	1800	1	395,000	395,000	20,000	20,000
2	**Single Leaf Motorised Sliding Gate (With Angle)**	6000	1800	1	367,000	367,000	20,000	20,000
3	**Wicket Gate (With Angle)**	4650	1800	1	37,500	37,500	10,000	10,000
4	**Motorised Telescopic Leaf Sliding Gate (With Perforated Sheet)**	4650	1800	1	427,000	427,000	20,000	20,000
5	**Single Leaf Motorised Sliding Gate (With Perforated Sheet)**	6000	1800	1	377,000	377,000	20,000	20,000
6	**Wicket Gate (With Perforated Sheet)**	4650	1800	1	40,500	40,500	10,000	10,000
7	**Boom Barrier(6 Mtr)**		6000	1	130,000	130,000	12,000	12,000
				Total				
2	P&F Charges			3%		-		
	Total Without Taxes					-		-
	GST Extra @ 18%			18%		-		-
	Total With Taxes					-		-
3	Transportation Charges					**In Client Scope**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No	Description	Specifications For Sliding Gate	Specifications For Sliding Gate
1	**Opening Direction**	Horizontal - from left to right or reverse	Horizontal - from left to right or reverse
2	**Mounting Location area**	Inside area	Inside area
3	**Perforation Sheet**	**Not Considered**	**Considered: 2 mm THK**
4	**Design Pattern**	Standard Tubular Design Pattern	Standard Tubular Design Pattern
5	**Outer Frame Tube Sizes**	72 x 72 x 3.2mm MS SQ. TUBE	72 x 72 x 3.2mm MS SQ. TUBE
6	**Internal Vertical Tube Sizes**	32 x 32 x 3.2mm MS SQ. TUBE	32 x 32 x 3.2mm MS SQ. TUBE
7	**Gap Between Tubes**	125 MM	125 MM
8	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
9	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
10	**Full Height Column sizes**	100 x 100 x 4mm MS SQ. TUBE	100 x 100 x 4mm MS SQ. TUBE
11	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	**Painting**	Powder Coating	Powder Coating
13	**El motor make**	BFT – Italy (100% imported)	BFT – Italy (100% imported)
14	**Emergency Operation**	Manual after turn the switch	Manual after turn the switch
15	**Operating Switch**	Push Button from inside	Push Button from inside
16	**Safety**	Photocells	Photocells
17	**Metal Rack**	Zinc plated metal rack	Zinc plated metal rack
18	**Installation Checks**	need to be check = space requirements + substructure + Mounting access + Access in the event of power cut	need to be check = space requirements + substructure + Mounting access + Access in the event of power cut
19	**Civil work**	Client scope – client need to grout the I beam in concrete to create track for sliding gate	Client scope – client need to grout the I beam in concrete to create track for sliding gate

BOOM BARRIER

Each Boom Barrier Set include:
MICHELANGELO BT A Barrier-1No.
- **Round Boom First part-1No.**
- **Round Boom Second part- 1 No.**
- **Anchor Base- 1No.**
- **MOB. Boom Rest-1No.**
- **Rubber Safety Profile- 1No.**
- **OMEGA AT Acce. - 1No.**
- **Transmitter with Channels- 1No.**
- **Push Button**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Ulka Auti
72519206333
For NIHVA Technologies Pvt Ltd