NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Asiss Packaging
Mumbai

Date : 13.12.2023
Quote NO : **MHE_23.24.0012**
Kind Attn : Mr. Sandesh Kadve
Email Id : sandesh@asisspackaging.com
Contact No: 9820186915

Project Name & Location: Asiss Packaging Project, Mumbai

Subject : Quotation for Telescopic Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Conveyor** • Total Length- 16000mm (Fixed-5500mm, Extended-9000mm) • Capacity- 70 Kg per mtr • Belt Width - 650 mm	1	20,70,000	20,70,000	75,000	75,000
	TOTAL EXCLUDING TAXES			20,70,000		75,000
2	GST Extra @ 18%	18%				Extra At Actual
3	P&F Charges	3%				Extra At Actual
4	Transportation Charges					In Client Scope
5	Insurance Charges					Extra At Actual
6	Unloading Charges @ Site					In Client Scope

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Conveyor

Sr. No.	Parameters	Specification
1	Capacity	70Kg per meter
2	Belt Width	650 mm
3	Belt Type	Smooth Top 2 Ply, PVC Coated Endless type
4	Length Of Conveyor	Fixed length(A) : 5500mm Telescopic (extended) : 9000 mm Total (B) : 16000 mm
5	Direction	Both Forward and Reverse direction
6	Inclination Height	Max. 950 mm
7	Gear Box	Bonfiglioli make
8	Driven Motor Make	Bonfiglioli make

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 No return policy applicable for customized products.

5 Site readiness delay considered upto 2months only. After that client is totally responsible for any material damage and it will be on chargable basis.

6 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost which will be 8-9% of total project amount.

D) Terms & Conditions

Price	: Ex Works Pune.
Delivery	: 12-14 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order. 20% before dispatch.
Validity	: Validity of Offer is 15days from the date of quotation.
Warranty	: 12 months from the date of supply.
Compensation Clause :	Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA a compensation of 25% of order value.

With Best Regards
Urmila Ghotre
7410169333
For NIHVA Technologies Pvt Ltd