NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Amara Raja Infra Pvt. Ltd
1-18/1/AMR/NR, Nanakramguda,
Gachibowli, Hyderabad - 500032

Date : 11.03.2021
Quote NO : SQT.20.21.3095
Kind Attn : Mr. Ashok Kumar C
Email Id : cak@amararaja.com
Contact No: 8772267938

Project Name & Location: M/S.HAVELLS INDIA LIMITED SriCity, AP

Subject : Quotation for Automatic Sliding Gate, Manual Swing Gate & Wicket Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Automatic Sliding Gate**	8000	1800	2	345,000	690,000	20,000	40,000
2	**Manual Wicket Gate**	2000	1800	2	30,000	60,000	8,000	16,000
3	**Bi-parting Manual Swing Gate**	6000	1800	2	95,000	190,000	15,000	30,000
				Total Value		**940,000**		**86,000**
				P&F Charges	3%	28,200		
				Total Without Taxes		**968,200**		**86000**
				GST Extra @ 18%	18%	174,276		15480
				Total With Taxes		**1,142,476**		**101480**
				Transportation Charges		**Extra at Actual**		
				Unloading Charges @ Site		**In Client Scope**		

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications

Automatic Sliding Gate

Sr .No.	Specification	Automatic Sliding Gate
1	Door type	Automatic Sliding Gate
2	Clear Opening gate dimension	(W) 8000 mm X (H) 1800 mm
3	Master Leaf Size	10000 X 1800 mm
6	Opening Direction	Horizontal - from left to right or reverse
7	Mounting Location area	Inside area
8	Design Pattern	Standard Tubular Design Pattern
9	Outer Frame Tube Sizes	80x80x3.2 MM THK SQ. TUBE
10	Internal Vertical Tube Sizes	32x32x2.6 MM THK SQ. TUBE
11	For Post	80x80x3.2 MM THK SQ. TUBE
12	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
13	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings
14	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
15	Painting	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
16	Control Panel	2 Nos Operating Station.(Motor Panel and Security Room)
17	Operation	Push Button
18	Accessories	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Photocell

Wicket Gate

Sr .No.	Specification	Wicket Gate
1	Door type	Manual Single Leaf Wicket Gate
2	Size considered	Clear opening - (W)2000 mm x (H)1800 mm
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Frame Tube Sizes	80 x 80 x 3.2 mm
6	Internal Vertical Tube Sizes	32 x 32 x 2.6 mm
7	Gap Between Tubes	100 mm C/C
8	Painting	2 Coats of EPOXY polyamide based enamel finish of approved Colour
9	Operation	Manually Opening

Manual Swing Gate -

Sr .No.	Specification	Manual Swing Gate
1	Clear Opening gate dimension	(W) 6000 mm x (H)1800 mm
2	Opening Direction	Inside OR Outside
3	Mounting Location area	Inside
4	Max no of leafs	Double leaf (left hand & right hand)
5	Design Pattern	Standard Tubular Design Pattern
6	Outer Frame Tube Sizes	80 x 80 x3.2 mm
7	Internal Vertical Tube Sizes	32 x 32 x 2.6 mm Placed at 100 mm
8	Bearing	Thrust bearing at bottom & ball bearing at top
9	Full Height Column sizes	80 x 80 x 3.2 mm
10	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Scope
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Price Pune

Delivery : 8-9 Weeks from the date of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% advance along with purchase order & balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of Installation.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333.**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd