WORK ORDER

Client:	
BHARAT FORGE LIMITED	
Address:	
MUNDHWA,PUNE,CANTONMENT, PUNE-411 036	

PO Number:	4601242979	**W. O. No-**	SO/23-24/023
PO Dated :	26.06.2023	**W. O. Date**	27.06.2023
PO Received Date	26.06.2023	**Sales Co ordinator**	Shailesh
Ref. Quotation:	SQT.23.24.0060R2	**Front Sales Person**	Santosh. Shinde

Dispatch Address:

BHARAT FORGE LIMITED
MUNDHWA,PUNE,CANTONMENT,
PUNE-411 036

A **Technical Terms:**

Sr. No	Description of Goods	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	Automatic Boom Barrier - 6 Mtr & RFID long range Reader 5 Mtr Minimum	No	1			0	Pending
					Total	0	

Non standard items/extra requirement, if any:	**Required user manual and test certificates**

B	**Commerical Terms:**			
1	**Payment Terms:**	Payment 100% against material delivery within 15 days		
2A	**Delivery Date as per PO:**	26.07.2023	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	In NIHVA Scope	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	In NIHVA Scope	**5B. Loading Charges:**	
6A	**Unloading Scope:**	In CLIENT Scope	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	In CLIENT Scope	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 months from the date of supply.		
9A	**Height arrangement Scope:**	In CLIENT Scope	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	In CLIENT Scope		
11	**GST:**	18%		
12A	**Installation Scope:**	In NIHVA Scope	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	NA		
15	**Documentation Required:**	Standard Handover Documents		
16A	**Total site visits required:**	one site visit required before installation	**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

GM	AGM	SALES	Operation	PROJECT	DESIGN	Date & Time
Mr. Ameet Kurhade			Mr. Kiran M			29-06-2023

Technical Specifications

Automatic DC DRIVE High Speed Boom Barrier

1) 6 meter alluminuim Boom
2) Opening closing time 1-2 sec.
3) Power Supply 230 V
4) IP55 Ingress Protection rate. Operating Temp 10 to +60 C
5) 24V DC Operating Voltage with 2hours power Backup
6) Remote 2 qty
7) Industrial manual Button 1 set.
8) Duty Cycle 100%
9) UHF Reader Long Range 5 Mtr - 2 Nos
10) SMPS 12V 2.5A for UHF Reader - 2 Nos
11) UHF Reader Stand Metalic 5feet - 2 Nos
12) UHF Sticker Tag AT ACTUAL AS PER VIHICLE COUNT - 6 Nos
13) 8 Port Giga Switch for Network - 1 No
14) RADAR Sensor - 1 No
15) SMPS 12V 2.5A for RADAR Sensor - 1 No
16) 2 Door Controller - 1 No
17) SMPS 12V 5A for Controller - 1 No
18) Resting Stand for Boom - 1 No