NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1725R1 **Date : 13.09.2019**

Dhoot Builders Pvt. Ltd.,Pune
302, Sanskruti Lifespaces, Next to My car Maruti,
showroom, Bhumkar Chowk, Wakad,
Pune - 411057.

Kind Attn: Dhanada Ambekar
Email ID: purchasedhootbuilders@gmail.com
Contact No: 9130036077

Project Name And Location : ADR Axles site, Rajgurunagar Khed .

Subject : Quotation for Motorized Rolling Shutter and Motorized Sliding Gate and Wicket Gate.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Motorized Rolling Shutter** **Technical Specifications:** **• GI Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 2.5 mm Thick MS Guide** **• Perforation Sheet** **• Hood Cover & Motor Cover : 0.9 mm Thick GI material** **• Indirect Drive** **• With Painting** **(Supply + Installation)**				
1	**Motorised Rolling Shutter** Size (W) 3000 mm x (H) 3500 mm	1	No.	101,000	101,000
2	**Motorised Rolling Shutter** Size (W) 3000 mm x (H) 4700 mm	1	Nos.	121,000	121,000
3	**Motorised Rolling Shutter** Size (W) 4500 mm x (H) 4500 mm	1	No.	153,000	153,000
4	**Motorised Rolling Shutter** Size (W) 4000 mm x (H) 6000 mm	1	Nos.	172,000	172,000
B	**MOTORISED SLIDING GATE** **(Supply + Installation)**				
	Sliding Gate -(W) 10000 mm X (H) 1800 mm **• For Post- 50x50x4.5mm MS SQ. TUBE** **• Outer Frame- 50x50x4.5mm MS SQ. TUBE** **• Inner Frame - 25x25x3.20mm MS SQ. TUBE** **• Gap Between tubes -100 MM**				
1	**Size : (W) 10000 mm X (H) 1800 mm**	1	No	455,000	**455,000**
C	**WICKET GATE** **(Supply + Installation)**				
	Sliding Gate -(W) 1340 mm X (H) 1800 mm **• Gap Between tubes -100 MM**				
1	**Size : (W) 1340 mm X (H) 1800 mm**	1	No	45,000	**45,000**

GST Pune	**27AAECN0437H1ZM**	**Grand Total**	**1,047,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST Extra 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

If there is any query please feel free to contact Mr. Ravindra Kharat on 8551096333.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd