NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune :

NIHVA Sales Quotation

SCON Projects Pvt. Ltd
Office No.1A, Harshal Corner, Plot No.5, Survey No.78, Left Bhusari Colony, Paud Rd., Kothrud
Pune - 411038 .

Project, Location : Innovatec, Pune

Date : 5.1.2021
Quote NO : SQT.20.21.2900R1
Kind Attn : Kamlesh Bhagade
Email Id : kamleshb@sconprojects.com
Contact No: 8308809561

Subject : Revised Quotation for Sectional Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Sectional Door Horizontal Lift**	2480	2980	1	240,000	240,000	15,000	15,000
2	**Sectional Door Horizontal Lift**	2500	3070	1	243,000	243,000	15,000	15,000
	Total			**2**		**483,000**		**30,000**
3	P&F Charges			0%		-		
	Total Without Taxes					483,000		30,000
	GST Extra @ 18%			18%		86,940.00		5,400
	Total With Taxes					**569,940**		**35,400**
4	Transportation Charges					Extra at atcual		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019


An ISO 9001:2015 Certified Company

GST Pune :

B) Technical Specification

Sectional Door







Sr. No	Specification	Sectional Door
1	**Vision Windows**	2 Nos at central panel
2	**Opening Direction & Mounting**	Horizontal lift
3	**Opening/Closing Speed**	CDM9 0,28 m/s
4	**Door Material**	GI Steel
5	**Panel Thickness**	42 mm Square Grid, steel sheet
6	**Filling**	CFC-free polyurethane
7	**Panel colour**	RAL 9002 Grey White Powder coated
8	**Door sealent**	All door sealants made of EPDM rubber, temperature resistant - 30/+70
9	**Panel Flame Retardent standrad**	Flame retardant polyurethane foam according DIN4102-class B2.
10	**Water Penetration**	EN 12425 class 3
11	**Air Permealibity**	EN12426 class 3
12	**Wind Load**	EN21424 class 3
13	**Thermal Transittance**	EN 12428 1.10W /m2K
14	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
15	**Door saftey**	Doors equiped with spring break device
16	**Incase of Power failuer**	Doors to be equiped with quick release fuction
17	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
18	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft
19	**Emergency Operation**	by Disengagement rope manual
20	**Operating Switch**	Up/Down Keypad + stopbutton
21	**Locks : Lock bolt**	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
22	**Environmental Green Product Declaration Certification**	As per ISO 14025 and EN 15804

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune :

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 14 - 15 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd