NIHVA TECHNOLOGIES Pvt.Ltd

SR .NO	DESCRIPTION	QTY	RATE
1	MANUAL MOBILE SCISSOR LIFT TABLE including,	1 NO	75200/-
	CAPACITY = 150 KGS		
	PLATFORM SIZE = 1800L X 900W		
	OVER ALL SIZE = 2100L X 1100W		
	MIN HEIGHT = 500 MM		
	MAX HEIGHT = 1500 MM		
	LIFT HEIGHT = 1000 MM		
	HYDRAULIC CYLINDER = BORE 50 X 350 STROKE (approx)		
	PUMP = MANUAL HYDRAULIC HAND OPERATED PUMP.		
	WHEEL = SWIVEL CASTOR NYLON WHEEL DIA 150 X 50 MM		
	TOTAL MFG COST TO NIHVA		

COST
75200/-
75200/-