NIHVA TECHNOLOGIES PVT. LTD.

Supply & Installtion of Telescopic belt conveyor		**Supplier Name**	**NIHVA Technologies**
Technical Specifcations - Telescopic Belt conveyor		**Contact No**	**Vijay 8551093333**
DOC REF	**STD-LE-BQ-R0-RFP-TELESCOPIC BELT CONVEYOR**	**Address**	**Pune maharashtra**
DRG NO	**LT000025**	**Manufacturer name**	**NIHVA Technologies**
LOGIC DOC	**NA**		

CMT POINTS- SUGGESTED BY CLIENT

#	Category	Description	Supplier Remark	Suggestion by supplier
1	General	Vendor to consider one set of spares(Refer annexure) in commercials. This is to be delivered along with machine.		
2	General	List of items to be covered in commercials is given in the annexure		
3	General	Vendor to commit the TAT in hours in case of breakdown calls unresolved by Customer. Time taken from complaint raising to technical resource on site to be 24 hours max		
4	General	Part replacement under warranty incase of part failure to be done within 7 days from the date of occurrence	OK	
5	General	Motor make SEW eurodrive	Ok	
6	General	Belt Forbo preferrable	Ok	
7	General	Siemen's PLC preferrable	Ok	
8	General	Quality certificate or equivalent report for own manufactured items like Rollers	Ok	
9	Control	HMI is required to identify the problems.	Ok 4 " HMI considered	
11	Control	Siemen's VFD preferrable	Ok 3 phase VFD considered	If we go for single phase VFD cost will reduce
12	General	Along with technical proposal, vendor to share the functional logics of the system		
13	Monitoring	Tower ligth with buzzer to be used for indicating device status (ready, stop or emergency stop)		

	SPARE ANNEXURE (Related to Pt.no.1)		**Supplier Remark**	
	ITEMS	**ORDER QUANTITY DETAILS**		
1	MOTORS +GEARBOX	1 nos per motor type	We will provide after PO approval	
2	CHAIN	Min length as installed in a TBC		
3	ROLLERS / SHAFTS	2 nos per roller type		
4	BEARINGS	5% of total installed quantities (min qty 1 nos)		
5	BELT	1 nos belt per type. If same type of belt with different lengths are available consider them as a separate line item		
6	PANEL ITEMS	1 nos all the panel components including but not limited to current protection devices, voltage protection devices, PLC and its accessories, drives , relays, push bottons, switches, HMIetc		
7	FIELD DEVICES	5% of total installed quantities (sensors, reflecting plates or stickers, emergency push buttons, emergency pull cords, isolater switches)		