NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Sandvik Asia Pvt. Ltd
Rishikesh Apartment, Mhatre Compound,
Mumbai-Pune Road,
Pune - 411012

Date : 09.12.2019
Quote NO : SQT/19-20/2292
Kind Attn : Mr.Nachiket Vaze.
Email Id : nachiket.vaze@sandvik.com
Contact No: 9727744905

Subject : Quotation for Flap Barrier.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
Option - 1	**Fully Automatic , motorised Flap barrier single flap 304 stainless steel or 316 stainless steel, Passage width: ≤550mm.**			1	145,000	145,000	12,000	12,000
Option - 2	**Fully Automatic , motorised Flap barrier , Double flpa, 304 stainless steel or 316 stainless steel, Passage width: ≤550mm.**			1	210,000	210,000	12,000	12,000
			Total					
3	P&F Charges			3%		-		
	Total Without Taxes					-		-
	GST Extra @ 18%			18%		-		-
	Total With Taxes					-		-
4	Transportation Charges					In Client Scope		
5	Unloading Charges @ Site					In Client Scope		

	Optional Accsessaries			
1	**Controller**	1	13,000	13,000
2	**Card**	1	25	25
3	**Card Reader**	1	4,000	4,000

B) Technical Specification

FLAP BARRIER GATE :

Technical Specification -
Size (L x B x H) - 1400 x 280 x 980 mm
Unlock Time - 0.2 Sec
Pass Rate - 35 person / min
Pass Width - 550 mm
Weight - 120 Kg
Mode - Fail Safe
Power Consumption - 30 W
Driving voltage - 24 V



NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333.** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd