RELIABLE
CONSTROTECH | ENTERPRISES

18/09/2018

PURCHASE ORDER

To,

M/s. NIHVA Technologies Pvt. Ltd.,
187, G-Block, Thermax Chowk,
MIDC Chinchwad, Pune – 411019.

Kind Attn.: Mr. Ravindra Kharat

Dear Sir,

We are pleased to place this purchase order on you for the supply of the following material in good condition at our site at Cummins India Ltd., Survadi Village, near Phaltan as per the details mentioned below.

Sr. No.	Item Description	Quantity	Unit	Rate	Amount
1.	**Motorized Rolling Shutter** Technical Specifications: • MS Slat: 1.0 mm Thick • Profile: Curved Type Profile with heavy duty Shaft • Guide: 2.5 mm Thick MS Guide • Hood Cover & Motor Cover: 0.9 mm Thick GI Material • Motor: German Make – Elero – Direct Drive ○ Rated Voltage: 400 Volts (3 Phase Voltage) ○ Rated Frequency: 50 Hertz ○ Rated Current: 6.7 Amperes ○ Rated Power Consumption: 1.4 KW ○ Degree of Protection: IP 54 ○ Permitted Temperature Range: -10 Degree Celsius to +40 Degree Celsius • Integrated Anti-Drop Device • Push Buttons for "Open-Stop-Close": 2 Nos. (1 No. on each side of the Shutter) • Emergency Operating Mechanism: Chain Drive				
	Size: (W) 4000 mm X (H) 4000 mm (Supply & Installation)	02	Nos.		
				Sub-Total	
				GST @ 18%	
				Total	
Amount in Words: Rupees					Only.

RELIABLE
CONSTROTECH | ENTERPRISES

Terms & Conditions:

1. The above mentioned rates are inclusive of all taxes and other costs.
2. Transport from your premises in Pune till the site location shall be paid extra as per actuals.
3. Warranty period shall be applicable for a period of 12 months from the date of supply.
4. Shop Drawings of the Motorized Rolling Shutters shall be submitted in advance to obtain the Client's Approval on the same.
5. Delivery Timeline: 5 to 6 weeks from approval of Shop Drawings.
6. Terms of Payment: 80% Advance along with Purchase Order, 10% Payment immediately on Delivery and Balance 10% on Installation.
7. Contact Person for Delivery: Mr. Suhas Dhake (Mobile: 9819959134) or Mr. Pravin Sarode (Mobile: 9819001449).
8. Delivery Address:
   M/s Reliable Constrotech Enterprises
   C/o India Parts Distribution Center,
   Cummins Megasite, Survadi Village,
   Taluka Phaltan, Dist. Satara – 415523.
   Landmark: Hotel Nisarg
9. Billing Address:
   M/s Reliable Constrotech Enterprises
   'Nandadeep' Bungalow, R.B.I. CHS. No. 2,
   Gavand Road, Naupada, Thane – 400602.
10. GSTIN: 27AFBPK8879H1ZX

Thanking you,

Yours truly,

For **"RELIABLE CONSTROTECH ENTERPRISES"**

Mr. Swaroop Kulkarni