**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**FORI Automation India**
Plot no. 34, T Block, MIDC, Bhosari, Pune - 411026

**Date : 17.10.2020**
**Quote NO : SQT/20-21/2785**
**Kind Attn : Mr. Somnath Kulkarni**
**Email Id :** skulkarni@foriindia.com
**Contact No: 7798982932**

**Subject : Quotation for High Speed Door RP300**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Option 1 : By Sea**<br>**Albany make Machine Protection Door RP300** | 1800 | 2000 | 3 | 7,05,000 | 21,15,000 | 20,000 | 60,000 |
| 1 | **Option 1 : By Air**<br>**Albany make Machine Protection Door RP300** | 1800 | 2000 | 3 | 7,47,000 | 22,41,000 | 20,000 | 60,000 |
| | | | | **Total** | | | | |
| 2 | P&F Charges | | | 3% | - | | | |
| | **Total Without Taxes** | | | | - | | - | |
| 3 | Transportation Charges | | | | Extra at actual | | | |
| 4 | Unloading Charges @ Site | | | | In Client Scope | | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

| Sr. No | Description | Details |
|---|---|---|
| | | **Albany make Machine Protection Door RP300** |
| 1 | Door version: | **Vertical Rapid Roller Door for machine protection.** |
| 2 | Side Frames: | **Aluminum anodized two parts, to have easy access to switches and service.** |
| 3 | Door blade: | **Rolltex Plus Curtain with RAL Blue 5002** |
| 4 | Bottom beam | **Aluminium anodized.** |
| 5 | Drive unit: | **Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)** |
| 6 | Opening / closing speed: | **Approx. max. 2,4 / 1,7 m/s** |
| 7 | Control system: | **MCC Vector Control** |
| 8 | Power suppy: | **3/(N)/PE 230/380/400/415 V, 50 Hz** |
| 9 | Safety features: | **pre running photocell.** |
| 9 | Photocell | **with Photocell** |
| 10 | Safety limit switch: | **1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.** |
| 11 | Window Type | **700 x 500 mm Anti UV Type** |
| 12 | Window Qty | **1 No** |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

**Note:** **Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D)** **Terms & Conditions**

| | |
|---|---|
| **Price** | : Ex works Pune |
| **Delivery** | : **By Sea :** 12 - 13 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.<br>**By Air :** 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval. |
| **Payment** | : 80% Advance along with Confirmed Purchase Order & Balance before dispatch. |
| **Validity** | : Validity of Offer is 15 days from the date of quotation |
| **Warranty** | : 12 months from the date of supply. |

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd