**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Anapurna Enterprises**
Mangalore, Karnataka

**Date : 29.08.2019**
Quote NO : SQT.19.20.1990
**Kind Attn : Mr. Pramod**
Email Id : pramod.kum009@gmail.com
Contact No: **8660973059**

**Project Name & Location:** Anapurna Enterprises; Mangalore,Karnataka

**Subject : Quotation for Goods Lift**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Length (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | Electro Hydraulic Goods Lift | 1000 | 1000 | 1 | 422,260 | 422,260 | 20,000 | 20,000 |
| | | | | **Total** | | **422,260** | | **20,000** |
| 2 | P&F Charges | | | 3% | | **12,668** | | |
| | **Total Without Taxes** | | | | | **434,928** | | **20,000** |
| | GST Extra @ 18% | | | 18% | | 78,287 | | 3,600 |
| | **Total With Taxes** | | | | | **513,215** | | **23,600** |
| 3 | Transportation Charges | | | | | **In Client Scope** | | |
| 6 | Unloading Charges @ Site | | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

| DETAILS | SPECIFICATION |
|---|---|
| Capacity | 300 KGS |
| No of Mast | I |
| Platform Size | 1000mmL x 1000mmW |
| Lowered Height | 200 MM |
| Lifting Height | 3660 MM |
| Cylinder Hydraulic | SINGLE ACTING CYLINDER |
| Hydraulic Cylinder | 63 Bore |
| Electric Motor | Siemens make 3HP |
| Valve Block | V tek |
| Tank Capacity | 70 Litre |
| Pump Capacity | 9 LPM |
| Power Supply | 415V |
| Hydraulic Hoses | Parker make |
| Pressure Gauge | Wika |
| Suction Strainer | Hydroline make |
| Bell Housing & Coupling | Hyzen make |
| Control Panel | NIHVA |
| Contactor | Siemens/ L& T |
| Overload Relay | Siemens/ L& T |
| Hose burst valve | STD |
| Phase Indicator | ITC/Ideal/Teknik |
| Hydraulic Power Pack | 7.5HP |
| Limit Switches | Teknik |
| Transformer | STD |
| Painting | STD-RAL 1004/ As per req. |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipments are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Filina
7410179333
For NIHVA Technologies Pvt Ltd