DATASHEET FOR GOODS LIFT

1.	Quantity	Three Nos.
2.	Capacity	2000 kgs
3.	Application	For installation inside our – for movement of packaging materials from GF to First and Mez. Floor;
4.	No. of stops / openings	03 stops / 03 Openings / Ground, First and Mezz. flr.
5.	Travel distance	15 Mtrs
6.	No. of Stops	3 nos
7.	Hoistway Size	VTA
8.	Car Inside dimensions	2800 mm Depth X 2200 mm Width X 2200 mm Ht. (VTC)
9.	Clear Opening on Shaft	2500 mm Width X 2000 mm Height
10.	Speed	0.50 m/s (VTC)
11.	Car Panels	C.S. Powder coated Finish Cabin
12.	Car Flooring	Aluminum chequered plate flooring
13.	Car Entrance	MS collapsible Door
14.	Landing Entrance	MS collapsible Door
15.	Overhead Available	2000 mm
16.	Pit Depth Available	Not available;
17.	Drive	VVVF with self-braking Geared motor
18.	Control	Microprocessor Based Down Collective With Soft Stop valve
19.	Signals	Position Indicators / Direction Arrows / Arrows with Scrolling
20.	Limit Switches	Limit switches for Over travel, Cabin entrance & exit doors
21.	Emergency Brake release device	Manual Brake release device required for emergency descent;
22.	Emergency Light and Alarm arrangement	Required

23.	Entry / Exit Pattern	Multiple entry/exit pattern
24.	Guide Rails	Machined, T-section rails of rolled mild steel having mirror finish.
25.	Suspension Ropes	ISI Marked, self lubricating type for car. USHA MARTIN or equivalent make;
26.	Safeties	Suitable Safety features to be provided to control the speed of the Lift and ensure operational safety of the system. These may include amongst others :
		a) Electromechanical type Gate locks for landing doors to ensure proper locking of the door before starting of the Lift.
		b) Car Gate Switch to be provided for the car door to enable running of the Lift only after proper closing of car door.
		c) Mechanical type Final Limit Switch to cut off the supply of the Controller in case of over running of the Lift.
		d) Earthing to be provided to the Car, Gate locks, Push button box, Guide rails to ensure electrical safety.
27.	Controllers	Suitable controllers shall be provided for trouble free operation and ease of maintenance;
28.	Wiring & Cabling	All wiring and cabling in the shaft way will be passed through metallic cable trays with requisite earthing to ensure safety of electrical Installation of the system.
29.	Buffer Spring	As an extra precautionary measure a pair of springs of appropriate compressibility, known as buffers are installed at the bottom of the shaft way to prevent the car from landing with a thud in case of snappage of suspension ropes, this, of course is a rare posssibility.
30.	Swing Doors at each Exit with electronic lock	Required
31.	Provision for Lockout Master switch	Required
32.	Overspeeding governor in case of wire rope failure	Required

33.	Operating Area classification	Safe Area;
34.	Power Supply	440 Volts, 50 Hz, A C Supply
35.	Light Supply	230 Volts, 50 Hz, A C Supply