







Quotation

ASSA ABLOY

ASSA ABLOY Entrance Systems

The global leader in door opening solutions

Sales Quotation

Quotation No. SQT/20.21/2668 R **Date: 31/08/2020**

V. M. Matere Infrastructure India Pvt.Ltd.
Borade Vasti, PCMC, Pune - 412105

Kind Attn: Mr. Nilesh

Email: 'nilesh.warang@vmmatere.com'

Contact No.: 7385486734

Project Name and Location: Hangar Door Service and Spares (Supply & Installation) at Pune Airport

Dear Sir,

Thank you for giving us an opportunity to participate with our offer on the above project. We enclose herewith our proposal which includes:

A. Requirement
B. Proposal
C. Terms and Conditions
D. Pricing

By choosing us as the supplier of your door automation products, you will receive the following advantages:

- You are working with a Global Provider with financial strength and over 50 years' experience of the global market place in Entrance Solutions.
- World leading products ensure excellent reliability and life-cycle costs to give you peace of mind.
- Project support for both specification development and design suitability
- A comprehensive product helping to provide value engineered solutions

We wish you success with your project and hope that we may be part of your current & future projects as a solution provider. We will follow up this quotation with a call to you within the next few days.

If you have any questions after reading this proposal, or if you need more information, please do not hesitate to contact us.

Kind Regards,
Ms. Smita Khare
NIHVA Technologies Pvt. Ltd
Mob: +91 9637991333
Email:nihvacare@nihva.com

Description: -

The door is operated via PLC based control panel. The enclosure of the control cabinet meets the specifications of protection class IP65, Push buttons IP65 and Gear motor IP55

Electrical cables as per EN regulations. Cable tray and/or conduit is excluded.

All other details are enclosed herewith in separate sheet.

Commercial Offer: -

Supply of Hangar door

Sr No.	Clear Size in mm (W) X (H)	Qty (in NO's)	Supply & Installation (Door + Structure) Price in INR	Total Qty	Total Amount
123 .04	**Dismantling and reinstallation of (W) 62000 mm x (H) 8500 mm** Dismantling/taking down P-165 Hanger opening (30.00mx8.50m) and a set of 06 doors (5.00mx8.50m) on each opening, in 305.00m opening 6 Equal leafs on each entries bi-parting i.e. 3 leafs each side and quoted rate included all damages made to the existing floor, roof etc shall be made good and match with the existing etc. complete all as specified and directed.	**1**	**1,52,000**	**2**	**3,04,000**
123 .03	**Dismantling of (W) 45000 mm x (H) 9000 mm** Dismantling/taking down P-01 Hanger opening (45.00mx9.00m) and a set of 06 doors (7.50mx9.00m) on each opening, in 45.00m opening 6 Equal leafs on each entries bi-parting i.e. 3 leafs each side and quoted rate included all damages made to the existing floor, roof ets shall be made good and match with the existing etc complete all as specified and directed.	**1**	**1,68,000**	**2**	**3,36,000**

123.40	**Dismantling of (W) 30000 mm x (H) 8500 mm** Dismantling/taking down P-70 Hanger opening (62.00mx8.50m) and a set of 08 doors (7.70mx8..40m) on each opening, in 62.00m opening 8 Equal leafs on each entries bi-parting i.e. 4 leafs each side and quoted rate included all damages made to the existing floor, roof etc. shall be made good and match with the existing etc. complete all as specified and directed.	**1**	**1,78,000**	**2**	**3,56,000**
123.05	Aligning of bottom tracks existing tracks, repair of ball bearing/ machining/ complete wheels necessary as required of all top and bottom wheel of same/ better specifications. The following components of the Hanger doors shall be repaired/ replaced where ever required. (i) Repair/ of all bottom wheels including Machining as required, by keeping alignments in right direction by removing form door leafs, Re-assembling of wheels, placing ball bearing, re-fixing on door leafs etc complete all as specified and directed	**216**	**290,0000**	**Each**	**580,0000**
123.06	Aligning of top tracks existing tracks, repair of ball bearing/ machining/ complete wheels necessary as required of all top and bottom wheel of same/ better specifications. The following components of the Hanger doors shall be repaired/ replaced where ever required. (i) Repair/ of top wheels including Machining as required, by keeping alignments in right direction by removing from door leafs, Re-assembling of wheels, replacing ball bearing, re-fixing on door leafs etc. complete all as specified and directed.	**216**	**290,0000**	**Each**	**580,0000**
123.07	Replacing of existing wheel with drive wheel, required two drive wheels for one opening. Drive wheel shall contain either gear on the flange portion or shall have chain sprocket arrangement as per OEM etc. complete all as specified and directed.	**6**	**975000**	**Per set**	**5,850,000**
123	**Hangar Door Work description:**				

	(i) Providing & fixing outdoor type fully enclosed weather protected complete, 3-phase new motorization system with suitable capacity of motor, fixing on door leafs system, with all required cabling, conducting, Limit switches. Audio/ Visual Alarm. The capacity of motor shall be minimum 3 H.P. The mode of operation shall be one master with Two slaves. (ii) Providing and fixing outdoor type weather protected fully enclosed control panel with LED push button switches with function (Forward-Reverse-Stop) & Motor Protection, Overload protection, safety switches, Emergency Stop, Key Selectors. (iii) Festoon cable carrier arrangements, hooter cum blinker safety switches, cleats, buffers, track cleaners, complete to work smoothly of existing manually sliding bi-parting hanger doors (iv) Exist termac floor near rail shall be repair with macro concrete of approved make. (v) Existing door paint remove/scrub down complete two coat camoflauge pattern paint should be applied over a coat of primer. Providing and fixing of limit switches for auto power cut at suitable fixed destinations of master leaf both in opening and closing situations. (vi) Providing of ldler braking system to be attached with motor gear system via chain sprocket assembly drive, chanical buffers, heavy cleats, conneters, EPDM Gaskets at centre leafs. Auto track cleaners to be fitted at bottom of all leafs. (vii) Providing and fixing of Manual declutching system for any emergency at a suitable height by twisting the mechanism with Handle Shaped LN key. (viii) Rectify alignment of bottom tracks till parking bay to make electric operation smooth and friction free. The bottom track should be straight till parking bay at both extremities. (ix) Rectifying alignment of Top guide channel till parking bay to make electric operation smooth and friction free till parking bay at both extremities. (x) Making all door leaf aligned and straight by taking down door leaf, with all alteration and of small sections all as required.				
	Total				**24,246,000**

Scope of supply

The scope includes: Design, production, delivery and Supervision or installation of door & structure.

AT client scope (exclusion of NIHVA): Any Civil work, Flooring, PEB roof work, 3rd party certification, additional PEB sheet, electrical connection, if any

I. Preliminary schedule

The schedule below is preliminary. The schedule times will change subject to the final choice of door design. Critical milestones are receipt of the LPO, receipt of the advance payment, final approval of shop drawings, and successful load test of the building and overall site readiness for the door installation.

Delivery time: 12-14 Weeks

Installation time is subject to site readiness, clear working area and delays by others. Detailed program will be agreed with our project coordinator.

II. Delivery conditions

Delivery of material will be coordinated with the client written construction schedule. The contractor is responsible for notification to Megadoor of any expected or actual delays in the agreed delivery date at least fourteen (14) days prior to the scheduled delivery. Without timely notification of changes in delivery dates, the contractor or contractor's representative will assume the responsibility of unloading and storing the provided materials in a manner to prevent damage of the materials.

III. Drawings

We will issue a full set of shop drawings for approval within 2 weeks of receiving the confirmed order and finalized design details

IV. Compensation clause

Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA compensation of 25% of order value.

General Pre-Requisites Required at Site

Prerequisites:

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery.

Limit of Supply

1.Provide place to store the material to be installed.
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation.
4. Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include below:

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service Technicians is in client scope
2.Any civil / masonry/structural work required to support are in client scope.

Terms & Conditions:

Payment	80% advance along with purchase order & balance before dispatch
P & F Charges	@3% on supply price
Transport	Extra at actual
Tax	GST @18%
Validity	15 days from the date of offer

Delivery	Within 12-14 weeks from the date of receipt of confirmed order, drawing approval & advance payment.
Insurance	Extra as applicable
Warranty	12 months from date of Supply
Client scope	➢ Once our project gets completed; for any additional work to & fro, lodging & boarding of our service technicians is in client scope. ➢ Any masonry / structural work required to support are in client scope ➢ Lifting equipment's in client scope
Compensation clause	Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA compensation of 25% of order value.
Others	Need to provide by client - clear opening mounting structures, any Civil work, electrical points and cables till doors, suitable safe Lifting Equipment's and Scissor lifts, Material and equipment storage secured space, fabrication and assembly space.

General conditions of Aircraft Hangar Door

1. Continuous uninterrupted access to any single door section or as agreed separately.

2. A clear floor area of 4 meters each side of the door leaf must be available during the curtain fitting process. The floor should be finished or if this is not possible, adequate temporary protection be made available to prevent damage to the curtain material.

3. 400 volt / 50Hz 3 phase isolator to be fitted to within 1 meter of the door main control panel. If not available at the start of installation, a temporary supply is acceptable. Any return visits to commission the doors due to permanent power not being available will be charged as appropriate.

4. Provision of 230 Volt power supply (by others) for hand tools.

5. A dry and secure area, not in direct sunlight, is to be provided for storage of the door components.

6. Access to site between 7 am to 6 pm six days per week. If this is not possible the installation programme may require amending.

7. Any storage costs for materials due to delays outside of Mega door's control will be charged to the main contractor.

8. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practices. We reserve the right to extend the period

accordingly.

9. Any passes required for the project, are the responsibility of the Customer and Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

Exclusions

The following items are not within our scope of works and are to be provided by others at no cost to NIHVA

1. Any passes required for the project, are the responsibility of the Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

2. Power supply and isolators adjacent to the control panels (to be done by electrical contractor).

3. Any Civil work is in client scope.

4. Conduits and Cable trays from the control panel locations to the door distribution boxes, mullion hoist units and door hoist units be provided. (to be done by electrical contractor). These are to be installed prior to the commencement of door installation.

5. A 400/230 power supply (permanent or temporary) must be provided (FOC) by the main Contractor during the installation of the door for power tools and testing of the door sections during erection.

6. A safe storage / pre-assembly area for the door materials (by main contractor).

7. Any additional tests or certification, which are not within our scope of works but may be required by the Consultant or Client, these will be carried out or provided, subject to the actual requirements but will be at additional cost (by main contractor).

8. Lifting Equipment's required for installation.

Please feel free to Contact Mr. Mr. Sagar Parkale on 8551095333 For any further Clarification / Information in this concern.

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd