WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client:	
SCON Projects Private Limited	
Address:	
Hissa No. 3/1, 3/3, 3/10, S.No. 116, Samarth House, Near Shell Petrol Pump Pune Bengalore highway, Warje, Pune, Maharashtra, 411058	

PO Number:	AQU-PO-HO-211009001	**W. O. No-**	SO/21-22/0103
PO Dated :	09-10-2021	**W. O. Date**	11-10-2021
PO Received Date:	11-10-2021	**Sales Co ordinator**	Shailesh
Ref. Quotation:	SQT.21.22.0109R5	**Front Sales Person**	Shrikant

Dispatch Address:

Aquapharm Speciality Products Pvt.Ltd.
Industrial Plot no K2/4, Additional Mahad Industrial area , tal- Mahad, Dist- Raigad 402302, Mahad, Maharashtra (India) 402302

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	**MS Motorised Single Leaf Sliding Gate W 9000 mm X H 2000 mm**	Door type - MS Motorised Single Leaf Sliding Gate Opening Direction - Horizontal - from left to right or reverse Mounting Location area - Inside area Design Pattern - Standard Tubular Design Pattern Outer Tube - 100 X 100 X 3.6 MM THK SQ. TUBE For Post - 100 X 100 X 3.6 MM THK SQ. TUBE Inner Tube - 40 X 40 X 2.6 MM THK SQ. TUBE Gap Between Tubes - 125 mm Bottom Rail on ground - dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams Bottom Rollers - Heavy Duty Bottom Wheel With both side Bearings (chorme plated) Guide Rollers supporter during Gate movement Painting - 2 Coats of EPOXY polyamide based enamel finish of approved colour El motor make - BFT – Italy (100% imported) Emergency Operation - Manual after turn the switch Operating Switch - Push Button from inside Safety - Photocells, Flashing Light	NOS	1		0	0	
2	**MS Manual Wicket Gate, W 1500 mm X H 2000 mm**	Door type - MS Manual Single Leaf Wicket Gate Mounting Location area - Inside area Design Pattern - Standard Tubular Design Pattern Outer Tube - 100 X 100 X 3.6 MM THK SQ. TUBE For Post - 100 X 100 X 3.6 MM THK SQ. TUBE Inner Tube - 40 X 40 X 2.6 MM THK SQ. TUBE Gap Between Tubes 100 mm Painting - 2 Coats of EPOXY polyamide based enamel finish of approved Colour Operation - Manually Opening	NOS	1		0	0	
						Total	0	

Non standard items/extra requirement, if any:

B Commerical Terms:

1	**Payment Terms:**	20% Advance, 70% against delivery after 21 Days after receipt of Bill at HO & Balance 10% after successful completion of work & submission of documents for handover within 7 days at site.		
2A	**Delivery Date as per PO:**	On Or Before 30-Oct-21 **To be completed within 3 weeks from Drawing approval**	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	NIHVA Scope	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	NIHVA Scope	**5B. Loading Charges:**	
6A	**Unloading Scope:**	NIHVA Scope	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	NIHVA Scope	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 Months from our Project Handover to Client		
9A	**Height arrangement Scope:**	CLIENT Scope	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	CLIENT Scope		
11	**GST:**	18%		
12A	**Installation Scope:**	NIHVA Scope	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	NO		
15	**Documentation Required:**	Test Certificate, Guarantee/ Warrantee Certificate, Literature, Training/Working Procedure, Contact person details for after sales service.		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	V.T.		S.B.	S.M.	G.P	