NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Precision Automation and Robotics India Ltd
Gat No.463A, 463B, 464, Village Dhangarwadi
Tal : Khandala, Dist. Satara - 412 801

Date : 12.05.2021
Quote NO : SQT.20.21.3087R1
Kind Attn : Amit Dalvi
Email Id : amitda@parirobotics.com
Contact No: 9822199850

Subject : Revised Quotation for Machine Protection Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Albany Make Machine Protection High Speed Door - RP 300**	1000	2400	2	860,000	1,720,000	20,000	40,000
2	**Albany Make Machine Protection High Speed Door - RP 300**	1500	2400	1	880,000	880,000	20,000	20,000
3	**Albany Make Machine Protection High Speed Door - RP 300**	1800	2400	8	898,000	7,184,000	20,000	160,000
			Total			**9,784,000**		**220,000**
4	P&F Charges			0%		-		
	Total Without Taxes					**9,784,000**		**220,000**
	GST Extra @ 18%			18%		1,761,120		39,600
	Total With Taxes					**11,545,120**		**259,600**
5	Transportation Charges					**Extra at actual**		
6	Unloading Charges @ Site					**In Client Scope**		
	Optional							
7	**D_CS_032 - Optional Price /Display - Display "Up-Stop-Down" delivered separately**			1	25,000	25,000		
8	**D_CS_032 - Optional Price /Upcharge for UV versio - 700x500mm window in UV version**			1	4,000	4,000		
9	**D_CS_032 - Optional Price / UK - Door support to mount the door only on a concrete floor or similar (not for doors with chain drive)**			1	68,000	68,000		
			Total			**97,000**		-
10	P&F Charges			3%		**2,910**		
	Total Without Taxes					**99,910**		**-**
	GST Extra @ 18%			18%		17,984		-
	Total With Taxes					**117,894**		**-**

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Albany make Machine Protection Door RP300

Sr .No.	Specification	Albany make Machine Protection Door RP300
1	**Door type**	High-speed roller door RapidProtect 300
2	**Daylight width**	1.800 mm / 1.500 mm / 1.800 mm
3	**Daylight height**	2.400 mm / 2.400 mm / 2.400 mm
4	**Side frame extension X-Level**	200 mm
5	**Door control system**	MCC VectorControl - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit
6	**Max. Opening Speed**	2,3 m/s
7	**Max. Closing Speed**	1,7 m/s
8	**Control box position**	Mounted next to the drive unit
9	**Control system position**	Without specification (quote only)
10	**Motor Position**	Without specification (quote only)
11	**Wind class**	1
12	**Side frame version**	Aluminium
13	**Bottom plate**	Delivered without bottom plates
14	**Bottom profile**	Aluminium
15	**Safety contact edge**	Pre running photocell at the bottom profile
16	**Photocell**	With photocell
17	**Crank**	With crank for manual operation
18	**Top roll material**	Aluminium
19	**Door curtain / colour**	RollTex Plus / Orange, similar to RAL 2009
20	**Window type**	Window 700X500 mm with yellow frame
21	**Window Quantity**	1
22	**Height:bott.edge to bott.prof.**	1.100 mm
23	**Motor cover**	Motor cover powder coated standard
24	**Top roll cover**	Top roll cover made of aluminium
25	**MCC type / display type**	Standard version / Prepared for display
26	**Power supply / Main switch**	400 V, 3-phase / With main switch
27	**Frequency**	50 Hz
28	**Mains connection cable length**	3.000 mm
29	**Combibox cable length**	3.000 mm
30	**Dry contact**	Dry contacts for signal door open / closed and door in operation
31	**Interface card**	Interface card mounted in MCC combi box made of sheet steel
32	**Safety limit switch (MP)**	Prepared for Schmersal switch 1 side
33	**Cable marking**	Including cable and component marking
34	**Documentation language**	English
35	**Documenation door**	English
36	**Documentation control system**	English
37	**Wiring plan**	English
38	**MCC display language**	English
39	**Special door**	Yes
40	**CE - Sign**	The CE Declaration of Conformity cannot be issued for doors without control systems and standard safety equipment.
41	**Reference no. special door 01**	321068
42	**Warranty**	1 Year

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

PLC program for function:

1	Hold-To-Run mode for open and close. Metal combibox 300x300x210mm without main switch, without interface card, terminals (Phoenix ST/STTB 2,5) and relays (Finder) instead. 6,5mm triangle lock (SZ2460.650).
2	2 pce relay for open and close door, electrical lock between open and close signal, and status signal back to customer (customer gives 24VDC signals).
3	4 pce relay for door opened, closed, ready for work and safety edge activated (250ms).
4	Wireing and single wire marking on both ends (PATO/EMT) in Combibox according to draft "22652_321068_PSA_RP300_SIDEFRAME/WALLMOUNTED".
5	2 pce M20 cable fittings in the bottom of combibox for power and control cable (4G1,5mm² and 12G1mm²). Protection cover for M12 plug on display cable (side frame).

Mechanics Application :

1	1 pce Limit Switch Pilz PSEN cs 2.1p purchase order number 540100
2	1 pce .Cable 10m for safety switch PSENcs 1.1p
3	Bracked for Combibox 300x300 D8000X0005

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10-12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Vijay Tarak on 8551091333**

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd