Motorized Rolling Sutter

Door type	Motorized Rolling Sutter
Clear Opening dimension (w) -- x (h) --	W)..... x (H) ..... std. dimension or non. std. dimension
Opening Direction	Vertical - from bottom to Top
Mounting Location area	Inside area
Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side Guides : Optional = On Concrete/Steel / Masonry
Opening/Closing Speed	0.1 m/sec
Door Material	
Curtain material	GI
Curtain Panel	The panel made of 1.0mm thick CRCA steel
Curtain panel size	75mm wide
Curtain Profile	Corrugation
Slat Thickness	0.9 mm to 1.2 mm (As per IS 6248)
Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h
Side Brackets	MS Plate 3 mm to 10 mm thick , as per the opening dimension
Hood Cover	Made of GI Sheet Thickness 0.8 mm with 25x25x3mm angle stiffener
Surface finish	
Painting	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
Options Available	Perforation in Slat Profile / Rolling Grill
Automation	
Control Type	Optional = Dead man / Pulse Control
Drive Unit & Mounting Type	Option 1) Electric Motor (Imported German Make) (Single Phase/Three Phase) - Direct Mounting on Shaft Option 2) Electric Motor (Imported China make) (single phase / three phase) - Indirect Mounting - Sprocket chain arrangement

91 8551091333 ☎ +91 20 66304033

Email: marketing@nihva.com

Emergency Operation	Option = Manual Hand Driven / Chain Wheel Drive
Operating Switch	Option = Push Button from inside / or do you need Outside also Option = Push Button / Key Switch From Outside
Integration optional	Option = need to interlock or integrate with other door or machine or Equipment
Accessories	Option = Flashing Light / Door line Safety Photocell Option = Remote Control with receiver
Installation Constraint any	Need to be check = space requirements + substructure + Mounting access + Access in the event of power cut