NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Sato Argox India pvt ltd
Bangalore

Date : 07.08.2021
Quote NO : **MHE_21.22.0029**
Kind Attn : Mr. Harikrishanan
Email Id : harikrishnan.k@sato-global.com
Contact No: 9620690247

Project Name & Location: Sato Argox India pvt ltd., Bangalore

Subject : Quotation for Telescopic Belt Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges considering 03 people for 03 days in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Belt Conveyor**	**1**	**10,30,000**	**10,30,000**	**30,000**	**30,000**
		Total		**10,30,000**		**30,000**
	P&F Charges	3%		**30,900**		
	Total Without Taxes			**10,60,900**		**30,000**
2	GST Extra @ 18%	18%				**Extra At Actual**
3	Transportation Charges					**Extra At Actual**
4	Insurance					**Extra At Actual**
5	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Product	Box/Bag
2	Product size max	Please specify
3	Product size min	Please specify
4	Product weight	40 kg
5	Conveyor capacity	Up to 50 kg/mtr
6	Speed of conveyor	Up to 25mtr/min
7	Conveyor infeed height	900 mm
8	Conveyor outfeed height	Adustable
9	Contact parts	MS powder coated
10	Non -contact parts	MS powder coated
11	Gear motor	Bonfiglioli
12	Foot	Spectra plast/ equivalent
13	Belt	PVC green belt(2M10-U0-V10)
14	Belt make	Forbo
15	Belt width	550 mm
16	Conveyor width	As per layout
17	Finish	Powder coated
18	Speed control through	VFD
19	Safety	Sensor and physical safety
20	Sensor	P & F

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd