NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

MHD Projects
P.O.Box. 880, PC-112, Ruwi,
Muscat, Sultanate of Oman

Date : 22.08.2019
Quote NO : SQT/19-20/1957
Kind Attn : Mr. Ashish Singh
Email Id : ashish.singh@mhd.co.om
Contact No: 968-71557546

Subject : Quotation for Sectional Doors and Cold Room Doors.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount
1	Insulated door	1600	3000	54	136,000	7,344,000
2	Insulated door	1200	2200	40	67,000	2,680,000
3	Cold room sliding door(80 mm thick)	2500	3000	6	129,000	774,000
4	Cold room sliding door(80 mm thick)	2500	4000	7	156,000	1,092,000
5	Motorized Cold room sliding door	1500	1300	4	358,000	1,432,000
6	Cold room hinged door	1000	2200	4	60,000	240,000
7	Cold room sliding door	1200	3000	4	123,000	492,000
8	Cold room sliding door	2500	3000	21	156,000	3,276,000
9	Cold room sliding door	2500	4000	6	210,000	1,260,000
10	High Speed door HS9010PFR	2500	4000	4	1,003,000	4,012,000
11	High Speed door HS9010PFR	3000	3000	3	972,000	2,916,000
12	Sectional Door	3500	3000	5	399,000	1,995,000
13	Sectional Door	4000	4000	5	429,000	2,145,000
14	Sectional Door	3000	4000	4	401,000	1,604,000
15	Sectional Door	2000	3000	1	386,000	386,000
16	Sectional Door	2400	2800	7	380,000	2,660,000
17	Inflatable Dock Shelter	3600	3755	10	447,000	4,470,000
				Total		**38,778,000**
18			P&F Charges	3%		1,163,340
			Total Without Taxes			39,941,340
			GST Extra @ 18%	18%		7,189,441.20
			Total With Taxes			**47,130,781**
19			Transportation Charges			In Client Scope
20			Unloading Charges @ Site			In Client Scope

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Insulated door	
	A multi-purpose door, food Processing facilities, Supermarkets, warehouses and particular in place with a mixture of walking and driving traffic. The door also helps reduce draught, dust and noise. It is maintenance-free and available with a number of different frames. Thickness: 40mm Insulation material: CFC-Free Foam Hinges: Made of saltwater-resistant anodized aluminium with 90° hold-open function. The hinges never require lubrication. Frame: 1mm Pre-Coated steel with installation holes and matching plastic caps. Bumpers: Made of black -polyethylene-height 300mm Squeeze Protection: The Door leaf is available with a food industry approved gasket on the rear edge of the door leaf.
Manual Sliding Door (80 mm thick)	
	Supply of Manual Sliding Door for Positive Temp. 80 mm thickness (Density 42kg/m3) with 0.6mm PPGI Finish , FDA Approved Gasket, Cladding and handle with Emergency opner , PPGI Wall Frame , Heavy duty Aluminium Track, Aluminium Door Profile , SS 304 Door Opener & Closure , Canopy , SS 304 Integrated Pad Lock arrangement , Rollers: - The rollers are made of POM (nylon). The roller brackets, the stud bolt, the washer and the nuts are made of SS.
Manual Sliding Door (150 mm Thick)	
	Supply of Manual Sliding Door for Blast Freezer Temp. 150 mm thickness (Density 42kg/m3) with 0.6mm PPGI Finish , FDA Approved Gasket, Cladding and handle with Emergency opner , ALU. Wall Frame , Heavy duty Aluminium Track, Aluminium Door Profile , SS 304 Door Opener & Closure , Canopy , SS 304 Integrated Pad Lock arrangement , Rollers: - The rollers are made of POM (nylon). The roller brackets, the stud bolt, the washer and the nuts are made of SS. Heating Arrangement: - Supplied with heating cables in both frame / threshold and door blade. The threshold which is manufactured of anodized aluminium is to be placed into the floor. Alternatively, the door can be upplied without a threshold, if supplied with extra heating at bottom of the door blade.
High Speed door HS9010PFR	
Area of use:	Inside
Material:	Galvanised steel
Colours:	8 standard colors - white, yellow, green, orange, red, gray, black, blue
Safety:	1) Photocells in side columns 2) Flexible soft bottom edge including wireless edge activator 3) Break-away and self-repair function
Vision Window	Single row with 400 mm Height
Operating speed:	Opening: up to 2,4 m/s ** Closing: 1,2 m/s
Wind load resistance:	Class 1 (300 Pa (N/m^2)
Water penetration:	Class 1 (30 Pa (N/m^2))
Air permeability:	Class 1 (24 $m^3/m^2/h$ at 50 Pa)
Thermal transmittance:	6,02 $W/(m^2K)$
Lifetime expectations:	1.000.000 cycles
Temperature working range:	-30°C +5°C

Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy	
1	Door type	1042P	
2	Clear Opening dimension	(W)3000 x (H) 5000 mm	
3	Opening Direction	90 Degree	
4	Type of Mounting	High Lift	
5	Door produced Based on which certificatio	Doors produced according to ISO 9000 or ISO 14000 certified	
6	Opening/Closing Speed	0.25 m/s	
7	**Door Material**	GI Steel with PUF inside	
8	Panel Thickness	42mm	
9	Panel colour	RAL 9002 Powder coated	
10	External surface of the panel	diamond grid design with a glossy finish at the section joints.	
11	inside surface of the panel	Monolithic surface on the inside of the door	
12	Broken cold bridge	Section joints with broken cold bridges	
13	Door sealent	All door sealants made of EPDM rubber.	
14	All Panel height	All panels should be 545mm high	
15	Panel Inside insulation metrial	Insulation material to be CFC free polyuretane foam.	
16	Panel Flame Retardent standrad	Flame retardant polyurethane foam according DIN4102-class B2.	
17	Steel component Material	All steel components to be electro galvanized	
18	Hinge Material	Glass fibre reinforced Polyamide	
19	Panel Thickness	42 mm	
20	Spring Material surface finish	Powder coated	
21	Water Penetration	EN 12425	class 3
22	Air Permealibity	EN12426	class 2
23	Wind Load	EN21424	class 3
24	Thermal Transittance	EN 12428 1.10W /m2K	
25	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
26	Door saftey device 1	Doors equiped with spring break device	
27	Door saftey device 2	Door equiped with pneumatic safety edge	
28	Door saftey 3	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding from a moving door	
29	Incase of Power failuer	One can operate the Door manually	
30	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W	
31	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft	
32	Emergency Operation	by Disengagement rope manual	
33	Operating Switch	Up/Down Keypad + stopbutton	
34	Environmental Green Product Declaration Certification	as per ISO 14025 and EN 15804	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 11 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Installation : Client Scope.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr.Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd