NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Jascon Engineering
P.O.Box 55795 Doha, Qatar

Date : 22.08.2019
Quote NO : SQT.19.20.1958
Kind Attn : Mr. Moawaz Samdani
Email Id : estimation.ms@jasconengineering.com
Contact No: +974-33384538

Project Name & Location: Police Station at Qatar

Subject : Quotation for RR3000ISO High Speed Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 , 3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA ASSA ABLOY High Speed Door RR3000ISO**	3000	4500	1	14,10,000	14,10,000	**Client Scope**	
				Total		**14,10,000**		-
4	P&F Charges			3%		**42,300**		
	Total Without Taxes					**14,52,300**		
	GST Extra @ 18%			18%				-
	Total With Taxes							-
5	Transportation Charges					**In Client Scope**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Door construction:	External High Speed Exterior-Door. Curtain with lamellas 200 mm height, made of sandwich panels with thermal separation, coated RAL 9006. Side frames steel galvanized with balancing system with partial self opening.
Door blade:	Made of sandwich panels with thermal separation, coated RAL 9006. Height = 200 mm. Double walled window-lamellas are made with aluminium anodised frame with polycarbonat windows. When painting the curtain, this frame is as well available in same colour with Reference 220857 with extra charge.
Drive Unit:	Motor IP 55, either RH or LH as an option.
Control system:	Frequency converter MCC with infomation display including foil keys open-stop-close; with main switch in separate box incl. power cable (standard length = height of door).
Speed:	Opening / closing up to 2,1 / 0,6 m/s.
Power supply:	3/N/PE 380/400/415/440/480 V; 50/60 Hz.
Safety device:	Light curtain in side frame up to height 2500mm; emergency hand lever for partial self opening.
Self-opening:	The door can be opened partially by releasing the brake manually.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 11 weeks for Dock Leveler & Rolling Shutter, 11-12 Weeks for Sectional Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 100% Advance along with Confirmed Purchase Order

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd