NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0053 **Date : 21-09-2017**

Orient Electric
82, 1st Floor, Okhla Industrial Estate
Phase-III, Okhla Industrial Area
New Delhi,110020

Kind Attn : Mr. Pulkit Achantani
Email : pulkit.achantani@orientelectric.com
Contact No : 9599782116

Subject : Quotation for Telescopic Conveyor

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
Telescopic Conveyor Make- Nihva (HSN CODE : 84289090)					
Technical Specifications	• Conveyor Type : Movable • Length of telescopic conveyor : 30-40 ft • Fixed length of Conveyor : 20 ft • Speed of the conveyor : 1 rpm to 20 rpm • Product to be Conveyed : Fans • Maximum Weight of Product : 20.70 kgs • Product Size: 29.65 (L) x 22.24 (W) x 12.95 (H)Inches • Size of Truck/Container : 40ft • Height of the loading Bay from road level: 4ft • Type of loading : Manual • Type of unloading : Manual • Belt Width : 30 inches • Castor wheels for manual movement	**1**	**No**	**35,00,000**	**35,00,000**

GST PUNE:	**27AAECN0437H1ZM**
GST GUJRAT:	**24AAECN0437H1ZS**

Amount in Words	**Total Amount**	**35,00,000**
	Rupees Thirty Five Lacs Only	

Image Attached for Reference



Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. All structure support is in client scope
3. Unloading from truck placement on site
4. Electrical connection for control panel.
5. NIHVA Will provided structure drawing only if required
6. ExistingRepair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3% Extra
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	10-12 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm Purchase Order & balance before dispatch
6	**Insurance**	:	Extra if applicable
7	**Tax**	:	GST: 28% on total supply value
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre

7709586333

For Nihva Technologies Pvt Ltd