NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

TRANS ENGINEERS INDIA PVT LTD
Gat No. 1552A & 1326A, Dehu-Alandi Road,
Shelar Vasti, Chikhali, Pune-411062

Project, Location : Pune

Date : 9.1.2021
Quote NO : SQT.20.21.2924R
Kind Attn : Chaitanya Kuila
Email Id : chaitanyakuila@transengineers.com
Contact No: 8956709129

Subject : Quotation for Gear Operated Single Skin Rolling Shutter & Steel Doors

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**GI Single Skin Gear Operated Rolling Shutter**	3000	2980	2	56,000	112,000	20,000	40,000
2	**Single Leaf Steel Door**	1200	2980	1	32,000	32,000	10,000	10,000
3	**Single Leaf Steel Door**	1200	2440	1	29,000	29,000	10,000	10,000
	Total			**4**		**173,000**		**60,000**
4	P&F Charges			3%		5,190		
	Total Without Taxes					178,190		60,000
	GST Extra @ 18%			18%		32,074.20		10,800
	Total With Taxes					**210,264**		**70,800**
5	Transportation Charges					Inclusive		
6	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Gear Operated Rolling Shutter

Sr .No.	Specification	GI Gear Operated Rolling Shutter
1	**Description**	Gear Operated Rolling Shutter with GI slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area
3	**Mounting Surface**	Side Brackets: On Concrete
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
11	**Surface finish**	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
12	**Operation**	Gear Assembly (Manual Handle)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 12 Days from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 90% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Amol Gaware on 7758820333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd