WORK ORDER

Client:	
Tenneco Clean Air India Pvt Ltd	
Address:	
Plot G6, Phase III, Chakan MIDC, Pune - 410501	

PO Number:	4502588469	**W. O. No-**	SO/22-23/044
PO Dated :	13-09-2022	**W. O. Date**	16-09-2022
PO Received Date:	16-09-2022	**Sales Co ordinator**	Shailesh
Ref. Quotation:	SQA.22.23.0176R2	**Front Sales Person**	Shailesh

Dispatch Address:

Plot G6, Phase III, Chakan MIDC, Pune - 410501

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	NIHVA MAKE Machine Protection Doors (W)1800 mm X (H)2000 mm	Sheet 2	Nos	2		0	-	Pending
						Total	-	

Non standard items/extra requirement, if any:	

B	**Commerical Terms:**			
1	**Payment Terms:**	50% ADVANCE, 40%+TAX AFTER GRN, 10% AFTER INSTALLATION		
2A	**Delivery Date as per PO:**	10 - 12 weeks from the date of receipt of confirmed purchase order; Advance Payment & Drawing approval.	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	CLIENT Scope	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	NIHVA Scope	**5B. Loading Charges:**	
6A	**Unloading Scope:**	CLIENT Scope	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	CLIENT Scope	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 months from the date of supply.		
9A	**Height arrangement Scope:**	CLIENT Scope	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	CLIENT Scope		
11	**GST:**	As Applicable		
12A	**Installation Scope:**	NIHVA Scope	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	NA		
15	**Documentation Required:**	Standard Handover Documents		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

GM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	V.T.		S.B.	C.C.	Sujata	17-09-2022

NIHVA make Machine Protection Door

Sr. No	Description	NIHVA make Machine Protection Door
1	**Door version:**	Vertical Rapid Roller Door for machine protection.
2	**Side Frames:**	Aluminum anodized two parts, to have easy access to switches and service.
3	**Door blade:**	2mm thick Curtain with RAL Blue 5010
4	**Bottom beam**	Aluminium anodized.
5	**Drive unit:**	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)
6	**Opening / closing speed:**	Approx. max. 2,0 / 1,5 m/s
7	**Control system:**	MR220 Controller with Inverter
8	**Power suppy:**	3/(N)/PE 230/380/400/415 V, 50 Hz
9	**Safety features:**	Safety edge with cable chain integrated in side frames, pre running photocell.
9	**Photocell**	with Photocell
10	**Safety limit switch:**	1 Euchner safety limit switch .
11	**Window Qty**	1 No