NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1658 **Date : 24.05.2019**

Himatsingka Linens
Plot No.1, KIADB Industrial Area, Gorur Road
Hanumanthpura Post, Hassan - 573201
Karnataka

Kind Attn: **Mr.Saravanan**
Email: saravanan.chakravarthi@himatsingka.com
Contact No: 9900093588

Project Name And Location :

Subject : Quotation for Tripod Turnstile

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer :

Option 1 :-

Sr No	Description	Qty	Unit	Rate In INR	Net Amount INR
	A. Tripod Turnstile : Semi Automatic Tripod with D Shape Tripod with 3 arms, 304 stainless steel or 316 stainless steel, with drop arm feature and Access Control Card Reader along with Bio Metric Device **Size : (L x B x H) 480 x 280 x 980 mm** **Unlock Time : 0.2 Sec, Pass Rate : 35 Person / Min, Pass Width : 550 mm,** **Weight : 45 Kgs, Mode : Fail Safe**				
1	Tripod Turnstile (Supply + Installation)	1	No	99,143	99,143
	Total				**99,143**

Option 2 :-

	B. Flap Barrier Gate : Turnstile featured with Sliding Flaps Operation principle. **Size : (L x B x H) : 1400 x 280 x 980 mm** **Unlock Time : 0.2 Sec, Pass Rate : 35 Person / Min, Pass Width : 550 mm,** **Weight : 120 Kgs, Mode : Fail Safe Along with Bio Metric Device**				
1	Turnstile (Supply + Installation)	1	No	234,900	234,900
	Total				**234,900**

Option 3 :-

	C. Flap Barrier Gate : Turnstile featured with Sliding Flaps Operation principle. **Size : (L x B x H) : 1400 x 280 x 980 mm** **Unlock Time : 0.2 Sec, Pass Rate : 35 Person / Min, Pass Width : 550 mm, Mechanism : Motorized** **Weight : 120 Kgs, Mode : Fail Safe Along with Bio Metric Device**				
1	Turnstile (Supply + Installation)	1	No	335,000	335,000
	Total				**335,000**

GST Pune : 27AAECN0437H1ZM

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	: Ex. Works Pune
2	**P & F Charges**	**:** @ 3% of Total supply value
3	**Freight Notes**	**:** Extra as applicable
4	**Delivery**	**: 3-4** weeks for Tripod Turnstile from the date of receipt of confirmed purchase order, Advance Payment and Drawing approval.
5	**Payment**	**:** 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	**:** Extra As applicable
7	**Tax**	**:** GST @18%
8	**Validity**	**:** Validity of Offer is 15 days from the date of quotation.
9	**Warranty**	**:** 12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat** on **07219207333** For any further Clarification / Information in this Concern.

With Best Regards

Smita Khare
9637991333
For Nihva Technologies Pvt Ltd