NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Laser Automation Pvt Ltd
40,Electronic Co-Operative Estate,
Opposite City Pride Theatre,
Pune Satara Road, Pune - 411 009

Date : 10.11.2020
Quote NO : SQT.20.21.2819
Kind Attn : Bindumadhav B Belsare
Email Id : info@laserautomation.in
Contact No: 9922944472

Subject : Revised Quotation for Machine Protection Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Machine Protection High Speed Door**	1300	1600	1	803,000	803,000	20,000	20,000
				Total		**803,000**		**20,000**
2	P&F Charges			3%		**24,090**		
	Total Without Taxes					**827,090**		**20,000**
	GST Extra @ 18%			18%		148,876		3,600
	Total With Taxes					**975,966**		**23,600**
3	Transportation Charges					**Extra at actual**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

High Speed Door RP2000



Sr. No.	Description	Specification
1	Door type	Machine Protection RP 2000
2	Description	Developed for Laser protection areas. Its Double walled slats prevent Penetration from Laser beams throughout the whole area of the curtain
3	Opening Direction	Vertical
4	Side Frame	Made of edged galvanized steel, all steel components galvanized, balancing system integrated in the side frames
5	Door curtain	Door curtain of ecru anodized aluminum lamellas, hingeless connected by means of flexible heavy belts, wear-less to wind up without to contact each other, each single lamella can be replaced easily, pre-fitted on the top roll.
6	Drive unit	Electical 1.1kw
7	Control system	Frequency converter control system MCC Vector Control, based on vector control including boost function at start-up. Graphic display and foil keypad for easy guided operation. Easy access to all important information for operation and service,
8	Protection	IP55
9	Suppply voltage	3L(N)PE/380/400/415/440/480V;50/60Hz Transformer necessary for 220/230/500V
10	Contol Voltage	24V Dc
11	Safety devices	Pre-running photocell with integrated cable chain in the side frames, drop down protection by integrated balancing system safety limit switch: magnetic switch with reader performance level e according to EN ISO 13849-1 and SIL3, according to EN 62061, switch integrated in side frame.
12	Manual activation	By releasing the brake at ground level. Depending on width/height ratio the door opens up to max. 2.0 m
13	Opening / closing Speed	(open/close) up to max. 2,0/1,2 m/s,

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd