WORK ORDER

NIHVA
NIHVA TECHNO GOUP PVT LTD

Client:	
Address:	
Gat. No. 408, village Urawade Taluka Mulshi, Pune - 412108	

PO Number:	220226	W. O. No-	SO/22-23/030
PO Dated :	28-07-2022	W. O. Date	29-07-2022
PO Received Date:	29-07-2022	Sales Co ordinator	Shailesh
Ref. Quotation:	SQA.22.23.0131R1	Front Sales Person	VT

Contact Details		Billing Address:	Dispatch Address:
Contact Person:		Gat. No. 408, village Urawade Taluka Mulshi, Pune - 412108	Gat. No. 408, village Urawade Taluka Mulshi, Pune - 412108
Email ID of contact Person:			
Mobile No:			

A — Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	Machine Protection Doors (W)4000 mm X (H)2500 mm	**Door version :**Vertical Rapid Roller Door for machine protection. **Side Frames :**Aluminum anodized two parts, to have easy access to switches and service. **Door blade:**Rolltex Plus Curtain (RAL5002) **Bottom beam:** Aluminium anodized. **Drive unit:** Drive unit IP 55, Motor on RH with control cable (standard length = height of door) **Opening / closing speed:** Approx. max. 2,4 / 1,7 m/s **Control system:** MCC Frequency converterVector Control for opening/closing speed up to 2,4 / 1,4 m/s for door with safety contact edge, protection IP 55. Without display, interface card delivered separately, including power- and interface cable, with main switch in separate box. **Power suppy:** 3L(N)PE 380/400/415/440/460 and 480 V, 50/60 Hz **Safety features:** Safety edge with cable chain integrated in side frames, door line photocell (Transmitter / Receiver) inside side frames, emergency crank and mechanical drop-down protection. **Safety limit switch:** 1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space. **Window Type:** 700 x 500 mm Anti UV Type **Motor & Hood Cover:** Included , **Motor at RHS** **Accessories :** Remote Control , **Display :** Display "Up-Stop-Down" **Interface Card :** MCC without display unit, with combibox in plastic (175x250x150 mm) with interface card and main switch included in combibox, including power- and interface cable.	Nos	2		0	-	Pending
						Total	0	

Non standard items/extra requirement, if any:	

B — Commerical Terms:

1	Payment Terms:	30% Advance against OA and Balance 30 Days PDC against receipt of Material.		
2A	Delivery Date as per PO:	On or Before 10.10.2022	2B. Required Delivery Date:	
3A	Transportation Scope:	CLIENT	3B. Transportation Charges:	
4	P&F Charges:	NIL		
5A	Loading Scope:	CLIENT	5B. Loading Charges:	
6A	Unloading Scope:	CLIENT	6B. Unloading Charges:	
7A	Lifting Equipments Scope:	CLIENT	7B. Available Lifting Equipments:	
8	Warranty:	12 months from the date of supply.		
9A	Height arrangement Scope:	CLIENT	9B. Available Equipments for working at Site:	
10	Electricity Supply:	CLIENT		
11	GST:	As Applicable		
12A	Installation Scope:	CLIENT	12B. Installation required date:	
13	Mode of import:	Sea		
14	HSS:	Yes		
15	Documentation Required:	High Sea Sale documents		
16A	Total site visits required:		16B. Site visit charges:	

Certified that the above work order finalised in presence of:

GM	AGM	SALES		Operation	PROJECT	DESIGN	Date & Time