Sales Quotation

Maple Leaf Electrovacs and Access Systems Pvt. Ltd.
Delhi

Date : 17.01.2020
Quote NO : SQT.19.20.2345R
Kind Attn : Ms. Anita Arora
Email Id : anita@mapleleafelectrovacs.com
Contact No: 9871103713

Project Name & Location: Flipkart: Delhi, mumbai, calcutta

Subject : Quotation for Dock Leveler, Rolling Shutter

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Dock Leveler Capacity 15 Ton**	2000	2985	126	200,000	25,200,000	7,500	945,000
2	**Motorised Rolling Shutter**	2500	3600	122	60,000	7,320,000	7,500	915,000
3	**Motorised Rolling Shutter**	3600	3600	2	80,000	160,000	7,500	15,000
4	**Dock Shelter**	3200	3400	126	69,000	8,694,000	5,000	630,000
				Total		**41,374,000**		**2,505,000**
				P&F Charges		**NIL**		
				Total Without Taxes		**41,374,000**		**2,505,000**
				GST Extra @ 18%	18%	7,447,320		450,900
				Total With Taxes		**48,821,320**		**2,955,900**

Transportation Charges for one truck at various locations

	Product	Delhi	Mumbai	Calcutta	per truck Qty
1	Motorised Rolling Shutter	55,000	18,000	85,000	**10**
2	Dock Leveler	55,000	18,000	85,000	**6**
3	Dock Shelter	55,000	18,000	85,000	**20**
4	Loading , Unloading Charges @ Site	**Including in above prices**			

Installation Time

For 126 Qty : 18 Weeks
For 30 nos lot : 5 Weeks

B) Technical Specification

Dock Leveler

Sr. No	Description	Specifications For 6 Ton
1	Required Capacity	6 Ton
2	Hydraulic Power pack	1 HP, 3PH
3	Control Panel	4 Push Button operated
4	Deck operation	By push button Deck UP & Deck Down
5	Lip operation	By push button Deck UP & Deck Down
6	Loading platform height from road Level	4 feet (1200 mm)
7	Travel above from Dock level height	350 mm
8	Travel below from Dock level height	200 mm
9	Deck platform size	2000mm (W) x 2985mm (L)
10	Lip sizes	400 mm
11	Clear Pit dimensions	2040mm (W) x 2985mm (L) x 485mm (H)
12	Drive type	Direct by electric Motor
13	Power Consumption	0.75 kw Motor
14	Degree of protection for motor	IP 55
15	Motor RPM	1410 rpm
16	Pump design flow	1.8 LPM
17	Pump pressure	200 bar
18	Safety valve set pressure	90 bar
19	Pump type	Gear
20	In built safety valve	Yes
21	Volume of oil receiver	8 Ltr
22	No of Deck Cylinders	2 Nos
23	Deck Plate Thickness	8 mm Chequered Plate
24	No of Lip Cylinders	1 No
25	Lip Plate	16 mm Thick Plate
26	Dock Bumpers	1 Pair included

Rolling Shutter

Sr. No	Description	Specifications
1	Rolling Shutter	Motorised Rolling Shutter with Mild Steel of thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Curtain Panel	The panel made of 1.0mm thick MS steel
4	Curtain panel size	75mm wide
5	Curtain Profile	Curved
6	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
7	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
8	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
9	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension
10	Hood Cover	Made of GI Sheet Thickness 0.9 mm GI mm with 25x25x3mm angle stiffener
11	Surface finish	PU paint or Powder coated
12	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting -Jielong

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
3	Any civil / masonry/structural work required	In Client Scope
4	All structure support required	In Client Scope
5	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
6	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : At Site

Delivery : 5 - 6 weeks for Dock Leveler & Rolling Shutter from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 8551093333**

With Best Regards
Varsha
8551091333