GAAS ENGINEERS PVT. LTD.
A 410 PUSHP BUSINESS CAMPUS,
VASTRAL, AHMEDABAD – 382418.
MOB – 9375040318, 9925004510

Our Ref. No. GEAA-2122-621
Date. 03.02.2022

To,
M/S, NIHVA TECHNOLOGIES
Pune

Kind Atten: - Mr. Vijay sir,

Technical data sheet of telescopic loading conveyor

PARTICULAR	DESCRIPTION
Material To Be Handle	Bags/Boxes
Weight Of The Bags/Boxes	40 Kg. maximum
Size of Bags/Boxes	Not specified , variable
Type	Collapsible Boom type hinged Telescopic Belt Conveyor
Design Capacity	50 kgs PER 1.5 METER
Size Of Belt	600 MM Width
Type Of Belt	Smooth Top 2 Ply, PVC Coated Endless type, (Imported)
Belt Speed – Fixed	25 to 30 Mtr. Per Minute
LENGTH OF CONVEYOR **3 BOOM**	**FIXED : 6500 MM** **TELESCOPIC : 12000 MM** **TOTAL : 18500 MM** **HEIGHT : as per drawing Submitted**

Main Body Of Conveyor	Manufacturing from 6 MM Thick. IS 226 Plate Material
Snub Pulley For Con.	Precision Machine from 3 Inch OD Schedule 40 Pipe With Inverted Bearing Fitted
Drive Pulley	Manufacture from 8 Inch ID Schedule 40 Pipe With Rubber Legging & hearing bone surface
Telescopic Movement	Mechanical arrangement
Mounting	On Fixed MS Chassis Mounted On fabricated frame with Cross Travel as per Drawing.
Height Adjustment ("Rexroth" parts)	With 2 HP power pack & cylinder for height adjustment,(ABB motor)
Panel (SEIMENS/SCHNEIDER) NO PLC	The conveyor comes with a fixed main panel on rear side and front side Wireless Remote operating panel with emergency stopper SWITCH, totally consoled wiring with digital counter and LED lighting
Painting	**INTERNAL:** Two coat of Epoxy red oxide and white paint.

	EXTERNAL: Two coat of primary & Two coat of high gloss Automotive paints.
DRIVE FOR BELT	**DESCRIPTION**
Belt Motor Fixed speed	**5 Hp, 1440 RPM, TEFC**
Motor Make	Bonfiglioli
Gear Box	Worm Type, Wall Mounted, With Suitable Ratio
Gear Box Make	Bonfiglioli
DRIVE FOR TELE. **MOVEMENT + VFD**	**DESCRIPTION**
Motor	**3 HP, 1440 RPM, TEFC**
Motor Make	Bonfiglioli
Gear Box	Worm Type, Wall Mounted, With Suitable Ratio
Gear Box Make	Bonfiglioli

GAAS ENGINEERS PVT. LTD.
A 410 PUSHP BUSINESS CAMPUS,
VASTRAL, AHMEDABAD – 382418.
MOB – 9375040318, 9925004510

Term & condition.

1. PRICE : - BASIC **12,90,000/-** EX WORKS. EXCLUDNG ALL OTHER LEVIS.
2. TAX: – GST 18% EXTRA AT ACTUAL.
3. TRANPORATION & INSURANCE: - AS EXTRA AT THE TIME OF DELIVERY.
4. PACKING FORWARING:- NIL
5. DELIVERY: - IN NORMAL CIRCUMTANCES **8 TO 10 WEEKS** FOR THE DATE OF CONFIRM ORDER WITH ADVANCE.
6. INSTALLATION : - THRU OUR TEAM CLIENT WILL HAVE TO PROVIDE NECCESSORY TOOLS N TACKELES WITH CRANE FACILITY, PLUS LOCAL TRANSPORTATION, LOADGING N BOARDING FACILITY, NEXT SERVICE CHARGE APPLICABLE RS. 10000/ PER DAY

7. WARRENTY : - 12 MONTHS FROM THE DATE OF DISPATCH.
8. PAYMENT TERMS : - 40 % ADVANCE WITH ORDER, 50% AT THE TIME OF DISPATCH AGASINT PROFORMA INVOICE & REMAINGING 10% AFTER INSTALLATION WITHIN 15 DAYS.
9. CANCELLATION : - ONCE PLACE ORDER WILL NOT CANCEL REASON WHATSOEVER IF THRUST UPON US AND ADVACNE AMOUNT WILL BE FORFITTED WITHOUT ANY CLAIM.
10. SUBMISSIONS : - ALL MECHINCAL & ELECTRICALS DIAGRAM AND MANUAL WILL BE. SUBMITTED AFTER SUCCESSFUL INSTALLATION.
11. VALIDITY:- 30 DAYS.

Loss / Transit damage: Intimation for the same should be given within 24 hours in written. Goods should not be opened. Damage notice to be put on the LR.

FOR, GET ENGINEERING AND AUTOMATION PVT. LTD.

KAMLESH MESVANIA
(DIRECTOR)