NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Amara Raja Infra Pvt. Ltd
1-18/1/AMR/NR, Nanakramguda,
Gachibowli, Hyderabad - 500032

Date : 09.03.2021
Quote NO : SQT.20.21.3088
Kind Attn : Mr. Brahmaiah Kota
Email Id : prasad.chavan@topband.in
Contact No: 9582333723

Project, Location : Ester Filmtech Limited , Greenfield BOPET Film facility at Hyderabad

Subject : Quotation for High Speed Door , Dock Leveler & Single Skin Galvalume Rolling Shutters

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Single Skin Motorised Rolling Shutter**	3500	4500	1	125,000	125,000	20,000	20,000
2	**Single Skin Motorised Rolling Shutter**	3500	5000	1	140,000	140,000	20,000	20,000
3	**Single Skin Motorised Rolling Shutter**	2500	4500	1	105,000	105,000	20,000	20,000
4	**Single Skin Motorised Rolling Shutter**	3000	3000	1	95,000	95,000	20,000	20,000
5	**Single Skin Motorised Rolling Shutter**	6000	6000	1	230,000	230,000	20,000	20,000
6	**Single Skin Motorised Rolling Shutter with Partly Grill -600 mm**	3500	4500	1	130,000	130,000	20,000	20,000
7	**Single Skin Motorised Rolling Shutter with Partly Grill -600 mm**	3500	5000	1	145,000	145,000	20,000	20,000
8	**Single Skin Motorised Rolling Shutter with Partly Grill -600 mm**	2500	4500	1	110,000	110,000	20,000	20,000
9	**Single Skin Motorised Rolling Shutter with Partly Grill -600 mm**	3000	3000	1	100,000	100,000	20,000	20,000
10	**Single Skin Motorised Rolling Shutter with Partly Grill -600 mm**	6000	6000	1	235,000	235,000	20,000	20,000
11	**RAPID ROLL-UP DOOR**	2500	4500	4	325,000	1,300,000	20,000	80,000
12	**RAPID ROLL-UP DOOR**	3500	4500	1	340,000	340,000	20,000	20,000
13	**RAPID ROLL-UP DOOR**	3500	5000	3	350,000	1,050,000	20,000	60,000
14	**RAPID ROLL-UP DOOR**	3000	3000	8	290,000	2,320,000	20,000	160,000
15	**Dock Leveler - 15 Ton UDL**	2000	2500	2	190,000	380,000	20,000	40,000
16	**Dock Bumper - 1 Pair**			1	8,000	8,000		-
	Total			**29**		**6,813,000**		**560,000**
	P&F Charges			3%		204,390		
	Total Without Taxes					7,017,390		560,000
	GST Extra @ 18%			18%		1,263,130		100,800
	Total With Taxes					**8,280,520**		**660,800**
	Transportation Charges					**Extra at atcual**		
	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

RAPID ROLL-UP DOOR

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels



Sr. No	Description	Specifications
1	Use	Internal Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening / Closing speed	Opening / Closing speed 0.8 m/s.
4	Control Panel	4 Push Button operated
5	Resistance to wind load	EN12424 upto class 2
6	Curtain	Fabric Transparent PVC section
7	Curtain colour	Standard blue RAL 5010
7	Guide Material	Galvanised steel.
8	Hood Cover	GI
9	Motor Cover	GI
10	Operator & Control	German Make Motor
11	Connecting Voltage	400 V ~ / 50 - 60 Hz
12	Open-Stop-Close Button	Standarad
13	Protection Category	IP 54
14	Power Consumption	0.75 kw Motor
15	Emergency Off Button	Standard
16	Closing Zone Monitoring	Optical Safety edge
17	External Route Monitoring	Photocell
18	Emergency Opening	Crank Handle

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Single Skin Motorised Rolling Shutter





Sr. No	Description	Specifications
1	Rolling Shutter	Rolling Shutter with Galvalume slat of thickness of 1.2 mm.
2	Mounting Location area	Inside area / Outside area
3	Curtain Panel	The panel made of 1.2 mm thick Galvalume slat
4	Curtain panel size	75mm wide
5	Curtain Profile	Curved with perforation at 0.5 mtr
6	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
7	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
8	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
9	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension
10	Hood Cover	Made of GI Sheet Thickness 0.9 mm GI
11	Surface finish	Powder coated
12	Drive Unit & Mounting Type	Electic motor - In direct Mounting - IP 54

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Make Dock Leveller





Sr. No.	Description	Specifications
1	Capacity	15 Ton - UDL
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 150 mm
7	Platform Size (W x L)	2000 mm x 2500 mm
8	Lip size (W x L)	2000 x 400 mm
9	Shut Height	480 mm
10	Maximum slope can be achieved	0.1
11	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L)2500 mm x (D)480 mm
12	Hydraulic power pack	Standard
13	Driver type	Direct by electric Motor
14	Motor Ratings	1 H.P
15	Pump design flow	2.5 LPM
16	Pump pressure	120 bar Operating 200 bar Max.
17	Safety valve set pressure	120 Kg/cm²
18	Pump Type	Gear
19	Volume of oil receiver	7 Lit
20	No Of Deck cylinder	2 No
21	Lip Cylinder	1 No

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 -12 weeks for Rapid Rollup Door & 5-6 Weeks For Rolling Shutters and Dock Leveler from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr Shrikant Mirkute on 8551098333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd