NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Date : 22.03.2021
Quote NO : SQT.20.21.3115
Kind Attn : Aishwarya Ambike
Email Id : inquiry.ho@rohanbuilders.com
Contact No : 020-71017101 Ext. 281

Client Name : Rohan Builders (India) Pvt. Ltd.
Address : 1 Modibag,Commercial Building,
Ganeshkhind Road, Shivaji Nagar, Pune – 411 016

Project Name & Location: M/s. Bodal Chemical Limited (Unit-V) Site SAYKHA-Gujarat

Subject : Quotation for Motorised & Gear Operated Rolling Shutters

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Options -1** _GI Motorised Rolling Shutter with 1 Year AMC	3000	4000	2	90,000	180,000	15,000	30,000
2	**Options -2** _GI Gear Operated Rolling Shutter with 1 Year AMC	3000	4000	2	70,000	140,000	15,000	30,000
				Total				
3	P&F Charges			3%		**Extra**		
	Total Without Taxes							
	GST Extra @ 18%			18%		**Extra**		**Extra**
	Total With Taxes					**-**		**-**
4	Transportation Charges					**Extra at actual**		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorised Rolling Shutters





Sr .No.	Specification	GI Motorised Rolling Shutter
1	Description	Motorised Rolling Shutter with GI slats with thickness of 1.2 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete
4	Curtain Panel	The panel made of 1.2 mm thick GI.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -as per w x h
10	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm
11	Surface finish	Powder Coated
12	Operation	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Gear Operated Rolling Shutter





Sr .No.	Specification	GI Gear Operated Rolling Shutter
1	Description	Gear Operated Rolling Shutter with GI slats with thickness of 1.2 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete
4	Curtain Panel	The panel made of 1.2 mm thick GI.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia as per w x h
10	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm
11	Surface finish	Powder Coated
12	Operation	Gear Assembly

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil structural work required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance against readyness of material before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Shrikant Mirkute on 8551098333.**

With Best Regards

Pradeep Shinde

8551096333

For NIHVA Technologies Pvt Ltd