NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0015 **Date : 08-06-2017**

Times Of India
Times Of India Building,
Dr D N Road, Fort, Mumbai
Maharashtra,India

Kind Attn : Mr.Kazim Zaidi
Email : c-kazim.zaidi@timesgroup.com
Contact No : 8960382391

Subject : Quotation for Scissor Lift

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.

This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
1	**Scissor Lift (Electro- Hydraulic)**				
Specifications	1. Platform Size: 2.27 x 1.12 mtr 2.Platform Extended: 1.5 mtr 3.Platform Height: 11 mtr 4.Maximum Load Capacity: 450 kg 5.Load on extended: 100 kg 6.Power source: 4 Batteries, 240v 7.Pair of scissors: 10 Nos.	1	Nos	8,70,000.00	8,70,000.00
	Total				8,70,000.00

VAT TIN :	27545250455 V
CST TIN :	27545250455 C
Service Tax No:	AAECN0437HSD001
GST ID:	27AAECN0437H1ZM

TOTAL BASIC AMOUNT	**8,70,000.00**
Rupees Eight Lacs Seventy Thousands Only	

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Intsallation charges is not included in above price.
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	Extra 3%
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	7-8 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm Purchase Order & balance before dispatch
6	**Insurance**	:	Extra
7	**Sales Tax**	:	Extra as applicable at the time of dispatch. Presently @13.5% VAT (supply within Maharshtra OR @2% CST against Form C (Outside Maharashtra)& GST if applicable
8	**Service Tax**	:	Extra @ 15%
9	**Validity**	:	Validity of Offer is 15 days from the of quotation
10	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre

2066304033

For Nihva Technologies Pvt Ltd