WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client: CLOOS INDIA WELDING TECHNOLOGY PRIVATE LIMITED	
Address:	Plot No. 114/1/3, General Block, MIDC Bhosari, Pune, Maharashtra 411026

PO Number:	LOI	W. O. No-	
PO Dated :	02.04.2020	W. O. Date	02.04.2020
PO Received Date:	02.04.2020	Sales Co ordinator	Varsha
Ref. Quotation:	SQT/19-20/2474R2	Front Sales Person	Bhavin

Contact Details		Billing Address:	Dispatch Address:
Contact Person:	Mr. Jayram Epilli	Plot No. 114/1/3, General Block, MIDC Bhosari, Pune, Maharashtra 411026	JCB India, Talegaon Pune
Email ID of contact Person:	Jayram.Epilli@cloos.de		
Mobile No:	7020780534		

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	Motorized Single Leaf Sliding Gate	• Width of 9500mm and Clear Height of 1800mm • 50X50X3 MM MS SQ. TUBE - OUTER TUBE • 50X50X3 MM MS SQ. TUBE - For Post • 11000X1900X0.9 THK - GI SHEET • Vision window - 500 x 500 mm • Safety : Photocell, flashing Light, Buzzer, Emergency STOP push button • Two coats of Primer and coats of Sythetic Enamel paint	No	2		0	-	Pending
						Total		-

Non standard items/extra requirement, if any:	ISMB supply will be in our scope

B Commerical Terms:

1	Payment Terms:	1. 40% Advance of Basic Amount immediately after release of PO 2. 40% + Full Taxes at the time of dispatch and inspection at suppliers place 3. Balance 20% of Basic Amount to be released after successful trials and completion of work on site with final signoff.		
2A	Delivery Date as per PO:	4 weeks from DAP	2B. Required Delivery Date:	-
3A	Transportation Scope:	To be paid extra as per actual at the time of Invoice or to be organized by Cloos, to be decided when material is ready for dispatch	3B. Transportation Charges:	-
4	P&F Charges:	NIL		
5A	Loading Scope:	NIHVA	5B. Loading Charges:	-
6A	Unloading Scope:	Client	6B. Unloading Charges:	-
7A	Lifting Equipments Scope:	NIHVA	7B. Available Lifting Equipments:	
8	Warranty:	12th Months from successful sign-off and handover.		
9A	Height arrangement Scope:	NA	9B. Available Equipments for working at Site:	N.A.
10	Electricity Supply:	Client		
11	GST:	Extra		
12A	Installation Scope:	NIHVA	12B. Installation required date:	-
13	Mode of import:	NA		
14	HSS:	NA		
15	Documentation Required:	Design, drawings, inspection reports, quality check certificate, bill of material, WC, Manuals		
16A	Total site visits required:	-	16B. Site visit charges:	-

Certified that the above work order finalised in presence of:

GM	AGM	SALES		Operation	PROJECT	DESIGN	Date & Time