	structural opening complete with all by-works as per specification, drawings, good engineering practice and directed by EIC. Partial grills and special stiffening members shall be provided wherever necessary. Area of clear structural opening shall be measured and paid for. The guide/hood/ hood cover area will not be measured separately for payment.				
CJ2RS1.4	Size 4000 mm (W) x 4500 mm (H)	Nos	2.00		
CJ2RS1.2	Size: 3500 mm (W) x 3500mm (H), partly grilled for 600 mm at a height of 900 mm from finished floor level. M.S. links 150 x 75 mm in the rolling grill portion with link opening of 115 x 45 mm.	Nos	2.00		
CJ2RS1.3	Size: 4000 mm (W) x 4500mm (H), partly grilled for 600 mm at a height of 900 mm from finished floor level. M.S. links 150 x 75 mm in the rolling grill portion with link opening of 115 x 45 mm.	Nos	1.00		
Sub Total					
GST				**-- %**	
Any Other Taxes (Please specify)				**--%**	
Total Amount for Carpentry & Joinery Works					

Total Amount Words :