# Sales Quotation

**Quotation No - SQT/19-20/1905R1** **Date : 07.08.2019**

**Intezine Lifestyle Pvt Ltd**
8, Bhalchandra apt,opp.
Telephone exchange Nal Stop Karve Road,
Pune - 411004

**Kind Attn: Mr. Nitin Bhosale.**
**Email:** accounts@intezine.com
**Contact No:** 9823757500

**Project Name And Location : Pune**

**Subject : Quotation for Tripod Turnstile and Flap Barrier Gate.**

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

**Commercial Offer :**

| Sr No | Description | Qty | Unit | Rate In INR | Net Amount INR |
|---|---|---|---|---|---|
| A | **Tripod Turnstile :**<br><br>**Small Footprint Requirement**<br>**Maximum Efficiency**<br>**Fast Responsive Motor**<br><br>**Technical Specification -**<br>**Size (L x B x H) - 480 x 280 x 980 mm**<br>**Unlock Time - 0.2 Sec**<br>**Pass Rate - 35 person / min**<br>**Pass Width - 550 mm**<br>**Weight - 45 Kg**<br>**Mode - Fail Safe**<br>**Power Consumption - 30 W**<br>**Driving voltage - 24 V** | | | |  |
| 1 | Tripod Turnstile<br>(Supply + Installation + Transportation) | 3 | Nos. | 81,000 | 243,000 |
| 2 | Controller | 3 | Nos. | 13,000 | 39,000 |
| 3 | Card | 1 | Nos. | 25 | 25 |
| 4 | Card Reader | 6 | Nos. | 4,000 | 24,000 |
| | **Total** | | | | **306,025** |

| | | | | | |
|---|---|---|---|---|---|
| B | **FLAP BARRIER GATE :**<br><br>**Technical Specification -**<br>**Size (L x B x H) - 1400 x 280 x 980 mm**<br>**Unlock Time - 0.2 Sec**<br>**Pass Rate - 35 person / min**<br>**Pass Width - 550 mm**<br>**Weight - 120 Kg**<br>**Mode - Fail Safe**<br>**Power Consumption - 30 W**<br>**Driving voltage - 24 V** | | | |  |
| 1 | FLAP BARRIERIER GATE<br>(Supply + Installation + Transportation) | 2 | Nos. | 303,000 | 606,000 |
| 2 | FLAP BARRIERIER GATE<br>(Supply + Installation + Transportation) | 1 | Nos. | 185,000 | 185,000 |
| 3 | Controller | 3 | Nos. | 13,000 | 39,000 |
| 4 | Card | 1 | Nos. | 25 | 25 |
| 5 | Card Reader | 6 | Nos. | 4,000 | 24,000 |
| | **Total** | | | | **854,025** |

**GST Pune : 27AAECN0437H1ZM**

**General Prerequisites Required at Site**

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

**Limit of Supply**

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

**Quote/Supply is based on**

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

**The supply included only those mentioned in the quote & does not include**

1. Unloading from truck placement on site
2. Electrical connection for control panel.

**Client Scope**

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

**Terms and Conditions :**

1. **Price** : Ex. Works Pune
2. **P & F Charges** **:** @ 3% of Total supply value
3. **Freight Notes** **:** Extra as applicable
4. **Delivery** **: 2-3** weeks from the date of receipt of confirmed purchase order, Advance Payment and Drawing approval.
5. **Payment** **:** 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6. **Insurance** **:** Extra As applicable
7. **Tax** **:** GST @18%
8. **Validity** **:** Validity of Offer is 15 days from the date of quotation.
9. **Warranty** **:** 12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat** on **07219207333** For any further Clarification / Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For Nihva Technologies Pvt Ltd