NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Marque Impex
Opp.Noorpur village, Chandusi road
Moradabad

Date : 31.08.2019
Quote NO : SQT.19.20.1939R
Kind Attn : Mr.Danish
Email Id : Admin@marqueimpex.com
Contact No: 9897874837

Project Name & Location: Telescopic Conveyor; Moradabad

Subject : Revised Quotation for Telescopic Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description
A.	Commercial Offer
B.	Technical Specification
C.	General Conditions
D.	Terms & Condtions

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Total length of conveyor (mm)	Width Of Conveyor (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Telescopic Conveyor	8000	810	1	779800	779800	50000	50000
				Total		**779,800**		**50,000**
2			P&F Charges	3%		**23,394**		
			Total Without Taxes			**803,194**		**50,000**
			GST Extra @ 18%	18%		140,364.00		9,000
			Total With Taxes			**943,558**		**59,000**
5			Transportation Charges			**In Client Scope**		
6			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Description	Specification
Total length of conveyor :	8000 mm
Collapsed length:	6000 mm
Telescopic Length:	3000 mm
Width Of Conveyor :	810 mm
Width Of Conveyor Belt :	750 mm
Conveyor Capacity:	50 kg / mtr
Speed:	5 mtr / min (Variable speed)
Drive Type :	
Conveying :	Auto/ Manual
Telescopic:	Auto/ Manual

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10- 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Swapnil Kulat on 7219207333**

With Best Regards
Pradip
7709586333
For NIHVA Technologies Pvt Ltd