NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Dinesh Remedies Ltd
Village Mahuvad, Haranmal Road,
Padra - Jambusar Highway, Taluka Padra District
Vadodara - 391440

Project, Location : Vadodara, Gujarat

Date : 8.1.2021
Quote NO : SQT.20.21.2939
Kind Attn : Ketan Bhatt
Email Id : ketan@dineshremedies.com
Contact No: 9727723259

Subject : Quotation for Dock Leveler and Mobile Manual Dock Ramp

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Dock Leveler 6 Ton Capacity**	2000	2500	1	230,000	230,000	15,000	15,000
2	**Mobile Manual Dock Ramp**	2100	12000	1	570,000	570,000	20,000	20,000
	Total			**2**		**800,000**		**35,000**
3	P&F Charges			3%		24,000		
	Total Without Taxes					824,000		35,000
	GST Extra @ 18%			18%		148,320.00		6,300
	Total With Taxes					**972,320**		**41,300**
4	Transportation Charges					Extra at atcual		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Dock Leveler

Sr .No.	Specification	
1	**Capacity**	6 Ton
2	**Dock operation mode**	AC power pack hydraulically operated
3	**Lip operation mode**	Hydraulic
4	**Operation control**	Through panel
5	**Loading platform height from road**	1250mm
6	**Travel above & below dock level**	(+) 300 / (-) 250 mm
7	**Platform Size (W x L)**	2000 mm x 2500 mm
8	**Lip size (W x L)**	2000 x 400 mm
9	**Shut Height**	480 mm
10	**Overall length**	2000mm x 2500mm + Lip Length (400mm)
11	**Maximum slope can be achieved**	10%
12	**Clear Pit dimensions (W x L x D)**	(W) 2000mm x (L)2500 mm x (D)485 mm
13	**Hydraulic power pack**	Standard
14	**Driver type**	Direct by electric Motor
15	**Motor Ratings**	1 H.P
16	**Pump design flow**	2.5 LPM
17	**Pump pressure**	120 bar Operating 200 bar Max.
18	**Safety valve set pressure**	120 Kg/cm²
19	**Pump Type**	Gear
20	**Volume of oil receiver**	7 Lit
21	**No Of Deck cylinder**	2 No
22	**Lip Cylinder**	1 No
23	**Yellow and Black Strips for Side**	Included

Mobile Manual Dock Ramp



Sr. No.	Description	Specifications
1	Railing	Across Length
2	Manual Flap	400 x 2000 (L)
3	Lip operation mode	Hydraulic
4	CI SWIVEL WHEEL	2 Nos.
5	Floor Lock	6 nos.
6	Rubber Tyre Wheel	2 nos.
7	Hydraulic Lift Cylinder	2 nos.
8	Hand Pump	Standard
9	Platform Size	(W) 2100 X (L) 12000
10	Ramp Capacity	10 Ton

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd