LP-29/D, 1st Floor, Maurya Enclave, Pitam Pura, Delhi-110034
Ph: +91-9990789996, 9818185152
Email: titensile@gmail.com / Web: www.titenclosures.com
Factory Address:- B129,130 Noida Phase II

Our Ref: WCTIE/Q/24-25/64
Date: 4/06/2024

To,

Nihva Technologies Pvt Ltd
Pune

Dear Sir

Thank you for your enquiry for the Automated pergola .

We are pleased to offer you the Automated roofing system from the world's leading manufacturing company " Suntech " from Turkey .

The below quote is based on the given drawings for the area to be covered as follows .

- 4000 x 5000 mm , (width) x (

  Projection) Client - Pune

We propose the model **EVA WITH LED lights** .

- Our roofing systems are suitable for any weather conditions , designed and built using highest quality materials. Our pergolas are manufactured using high grade aluminium profiles and stainless steel components in Anthracite colour .

- These systems are covered under a warranty of 5 years & can withstand wind speeds of 117 Km/hr .
- Each and every system is customised as per the size and the needs of the project utilising European technology through a custom direct drive motor system to ensure smooth and quick operation at 26 RPM .
- The optional high powered LED – TEC lighting system provides a practical touch of class & when coupled with a remote dimming controller allows the user to change the mood to suit the surrounding environment .
- Suntech systems are available in widths up to 13 meters & maximum projection of 11 meters in one fabric – providing a solution to cover areas up to 143 Sq. mts. at the touch of a button.
- The fire rated 100% water proof fabric from Mehler (Germany) is available in NTRB 33 Black providing maximum stability & resistance to temperature, moisture & dirt . It does not shrink or bag, and the acrylic top coating makes it very easy to clean .

We have now been erecting and commissioning Suntech systems for the last two year and have done several projects in India . To name a few : -

- Coconut Creek Resorts – Goa
- Hotel Marina – Shimla
- Goel Ganga Developers – Pune
- Private house – Shantinekatan – New Delhi
- Private house – Aralias – Gurgoan
- Private house – Golf Links – New Delhi
- Private house – Bhopal
- Hotel Empressa - Mumbai
- Private House – Gurgaon

Price : -

Supply of Suntech automated pergola system (Model EVA) 4,000 x 5000 mm	: Rs. 4,15,720
Standard Led lights	: Rs. Included
Installation	: Rs. 40,000
Steel Structure	:Rs. Not required
Total	: Rs. 4,55,720

- On approval of the quote, we would provide complete Acad drawings for the same which need to be counter signed .
- Time required is 45 days on receipt of advance .
- Civil work , electrical cabling and conduting is out side our scope of work .
- Transportation from Noida to site is on consignees account

- Installation time is 4 days .
- The above quote is based on installation on ground floor . Any movement of material from ground to respective floor will be on client's account .
- Scaffolding to be provided by the client .

Payment Terms:-

1. 65% advance with Po

2. 25% before dispatch.

3. 10% after completion

For **TI Tensile Structures.**

S/d

Ajay Khanna

9818185152