NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Admorp Engineering Services.
Bangalore -560097

Project, Location :

Date : 10.02.2021
Quote NO : SQT.20.21.3009
Kind Attn : Chandrashekhar R. Patil
Email Id : c.r.patil2096@gmail.com
Contact No: 9964352446

Subject : Quotation for Portable Electro-Hydraulic Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**PORTABLE ELECTRO-HYDRAULIC SCISSOR LIFT 1500 KG**	800	1200	1	220,000	220,000	15,000	15,000
	Total			**1**		**220,000**		**15,000**
2	P&F Charges			3%		6,600		
	Total Without Taxes					226,600		15,000
	GST Extra @ 18%			18%		40,788.00		2,700
	Total With Taxes					**267,388**		**17,700**
3	Transportation Charges					Extra at atcual		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Electro Hydraulic Mobile Scissor Lift

Sr. No	Description	Specifications
1	Capacity	1500 KG
2	Platform size	1200 mm(L) X 800 (W) mm
3	Shut ht	500 mm
4	Max ht	2000 mm
5	Lift ht	1500 mm
6	Power pack (RAL 1004)	1 HP, 3 Phase (1.8 LPM)
7	Color	GOLDEN YELLOW
8	Control Panel	1 HP STD
9	Hydraulic Cylinder	APPROX BORE 50mm Stroke 500 mm 2 nos
10	Hose and Hardware	3 / 8 BSP

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd