NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

DELICIA FOODS (Mfg.Franchisee-M/S Monginis Foods Pvt.Ltd.)
F/4, Krishna Complex, Next to Hari Har Corp. Compound,
Mankoli Naka, Post Dapode, Tal. Bhiwandi, Dist. Thane.

Project, Location :

Date : 02.03.2021
Quote NO : SQT.20.21.3068
Kind Attn : Sagar Mohite
Email Id : sagar.mohite@monginis.net
Contact No: 8369555945

Subject : Quotation for Auto Sliding Cold Room Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Auto Sliding Cold Room Door**	4000	2500	3	384,000	1,152,000	15,000	45,000
	Total			**3**		**1,152,000**		**45,000**
2	P&F Charges			3%		34,560		
	Total Without Taxes					1,186,560		45,000
	GST Extra @ 18%			18%		213,580.80		8,100
	Total With Taxes					**1,400,141**		**53,100**
3	Transportation Charges					Extra at Actual		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Auto Sliding Cold Room Door

Sr. No	Description
1	120 mm Puff Infill with 45 + Density 3D application door for Negative application uptill -22 degree.
2	PUFF Insulation 45kg
3	PCGI sheet thickness 0.6mm
4	120mm door thickness, with C-flushing, wall frame.
5	Pad lock Locking arrangement along with emergencyrelease system.
6	off white color, with door frame.
7	Smart Automation European make with Safety Device & Photo Cell
8	Push Button & Pull Cord on both side.
9	Provision for autoation in future with extended track and heavy duty reinforcement.
10	DC Motor with 240/v Single phase with Control Panel
11	Photocell, Door Safety Device

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 4 weeks for High Speed Door and 2 - 3 weeks for Sliding doors from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd