**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Patvin Engineering Private Limited**
Patvin House, W-193, TTC Industrial Area,
MIDC Khairane, Navi Mumbai - 400 709

**Project, Location : MSIL-Gurgaon**

**Date :** 20.08.2021
**Quote NO :** SQT.20.21.2669R4
**Kind Attn :** Mr. Pranav Vaidya
**Email Id :** pranav_vaidya@patvin.co.in
**Contact No:** 8828198478

**Subject : Revised Quotation for Fire rated Sliding Door at Maruti Suzuki Plant**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | Sliding Type Door (Fire Rated 120 min) | 1700 | 2100 | 1 | 150,000 | 150,000 | Inclusive | |
| | **Total** | | | **1** | | **150,000** | | **-** |
| 2 | P&F Charges | | | 0% | | - | | |
| | **Total Without Taxes** | | | | | 150,000 | | - |
| | GST Extra @ 18% | | | 18% | | 27,000 | | - |
| | **Total With Taxes** | | | | | **177,000** | | **-** |
| 3 | Transportation Charges | | | | | Extra at atcual | | |
| 4 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Fire Rated Sliding Door**

| Sr. No | Description | Specification |
|---|---|---|
| 1 | **Description** | BS 476 part(20 & 22)tested at CBRI :Central Building Research Institute, Roorkee |
| 2 | **Wall Opening(w)- mm** | 1700 mm |
| 3 | **Wall Opening(H)- mm** | 2100 mm |
| 4 | **Insulation** | Honeycomb/Rockwool |
| 5 | **Frame & Shutter Material** | GI |
| 6 | **Frame & Shutter Finish** | Powder Coating |
| 7 | **Fire rating** | 120 Minute (2 Hours) for Integrity and stability. |
| 8 | **Accessories Included** | Fusible link, wire rope, guide rail, counter weight, pulleys as per BS 476, Part 20 & 22 and standard accessories included |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description |
|---|---|
| 1 | Secured and fully covered Store area to keep the material |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site |
| 3 | Electrical Supply on the site single phase/three phase points at different places. |
| 4 | Any civil / masonry/structural work required |
| 5 | All structure support required |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. |
| 7 | Conduits, Cables required |

**D) Terms & Conditions**

**Price** : Ex Works Pune
**Delivery** : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
**Payment** : 30% Advance along with Confirmed Purchase Order, 60% Balance before dispatch and 10% after Installation.
**Validity** : Validity of Offer is 15 days from the date of quotation
**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

**With Best Regards**
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd