NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Denasa Buildcon
C-3, Sant Tukaram Vyapar Sankul, First Floor
Sector 24, Pradhikaran, Nigdi, Above Hotel Savali,

Project, Location : Sanand, Gujarat

Date : 13.02.2021
Quote NO : SQT.20.21.3017
Kind Attn : Mahesh Pawar
Email Id : mahesh.p@denasaindia.com
Contact No: 8308810541

Subject : Quotation for Motorized Rolling Shutters and Wicket Gates

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Rolling Shutter**	6000	6000	14	231,000	3,234,000	20,000	280,000
2	**Motorized Rolling Shutter**	3400	4200	1	121,000	121,000	20,000	20,000
3	**Motorized Rolling Shutter**	4100	4200	1	135,000	135,000	20,000	20,000
4	**Motorized Rolling Shutter**	4400	4200	7	141,000	987,000	20,000	140,000
5	**Motorized Rolling Shutter**	5100	4200	1	155,000	155,000	20,000	20,000
6	**Wicket Gate**	1000	1350	1	45,000	45,000	10,000	10,000
7	**Wicket Gate**	1270	1600	1	50,000	50,000	10,000	10,000
	Total			**26**		**4,727,000**		**500,000**
8	P&F Charges			3%		141,810		
	Total Without Taxes					4,868,810		500,000
	GST Extra @ 18%			18%		876,385.80		90,000
	Total With Taxes					**5,745,196**		**590,000**
9	Transportation Charges					Extra at atcual		
10	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	Description:	Motorised Rolling Shutter with GI Slats with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick GI.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick.
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm
12	Surface finish	Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Wicket Gate

Sr .No.	Specification	Wicket Gate
1	Door type	Manual Single Leaf Wicket Gate
2	Size considered	Clear opening - (W)1200 mm x (H)1800 mm
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Frame Tube Sizes	80 x 80 x 3.2 mm
6	Internal Vertical Tube Sizes	40 x 40 x 2 mm
7	Gap Between Tubes	100 mm C/C
8	Painting	2 Coats of EPOXY polyamide based enamel finish of approved Colour
9	Operation	Manually Opening

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd