Sales Quotation

Quotation No - SQT/19-20/1749 **Date : 26.06.2019**

Progressive infra project pvt. Ltd.
2nd Floor, Sai Niketan,
S. No.31/ 1A/2-C, Opp. Mega Mart
Old Pune -Mumbai Highway ,
Dapodi, Pune- 411012

Kind Attn : .Mr. Sumeet Patil
Email ID : purchase@pipil.co.in
Contact No : 7875337746

Project Name And Location : Pune.

Subject : Quotation for Three Leaf Motorized Telescopic Sliding Gate & Wicket Gate.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Three Leaf Telescopic Motorised Sliding Gate** **(Supply + Installation)**				
	Telescopic Sliding Gate - (W) 9000 mm x (H) 2100 mm **• OUTER TUBE - 72 x 72 x 3.2mm MS SQ. TUBE** **• INNEAR TUBE- 38 x 38 x 2.6mm MS SQ. TUBE** **• FOR POST - 72 x 72 x 3.2mm MS SQ. TUBE**				
1	Size (W) 9000 mm x (H) 2100 mm	1	No	757,000	757,000
B	**Wicket Gate** **(Supply + Installation)**				
	Wicket Gate - (W) 1500 mm X (H) 2100mm **• OUTER TUBE - 72 x 72 x 3.2mm MS SQ. TUBE** **• INNEAR TUBE- 38 x 38 x 2.6mm MS SQ. TUBE** **• FOR POST - 72 x 72 x 3.2mm MS SQ. TUBE**				
1	Size (W) 7200 mm x (H) 2200 mm	1	No	45,000	45,000
GST Pune	**27AAECN0437H1ZM**			**Grand Total**	**802,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with confirm purchase order & Balance 20% before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST Extra 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact Mr. Ravindra Kharat on 7410169333 for any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For Nihva Technologies Pvt Ltd