NIHVA TECHNOLOGIES

WEIGHT ESTIMATION SHEET

CLIENT			MAY-2024-ENQ-NTPL-2027			DATE	30-05-2024	
PROJECT			ELECTRO HYDRAULC SCISSOR LIFT			LOCATION	Pune	
FINISH SIZE - Min HT (C) -1250mm, Lift HT (D) -4750mm, Railing HT - 900mm			Platform (A) - 1500*2700mm			PREPARED BY	Bheemappa	
SR.NO	DESCRIPTION	SIZE	MTL	MTR	NOS	WEIGHT MTR/NOS	TOTAL WEIGHT	
1	ismc	100 x50	MS	8.4		9.5	79.8	
2	isa	50 xx50 x 4thk	ms	14.1		3.1	44.3	
3	ismc	75 x 40	MS	5.4		7.0	37.8	
4	r, tube	100 x 50 x 5thk	MS	34.2		10.6	362.4	
5	ismc	125 x 65	MS	8.4		13.0	109.2	
6	r, tube	100 x 50x3.5	MS	6		8.2	49.5	
7	r, tube	80 x 40x3.2	MS	6		6.0	36.2	
6	isa	50 xx50 x 4thk	ms	9		3.1	28.3	
7	ismc	126 x 65	MS	4.8		13.0	62.4	
8	ismc	75 x 40	MS	8.4		7.0	58.8	
9	isa	40 x40 x5thk	ms	14.1		3.1	44.3	
10	cyl pl	125 x 16	MS	1.6		15.7	25.1	
11	PIVOT pl	125 x 16	MS	0.96		15.7	15.1	
12	turn pl.	300 x 12	MS	0.6		28.3	17.0	
13	ALUMINUM Checkered plate	1500 x 4thk	MS	5.4		53.1	286.7	
14	Pipe	od 40x3	MS	15.6		4.0	62.4	
18	PIVOT PIN	DIA 25	EN8	2.4		3.9	9.2	
19	P BUSH	DIA 45	MS	0.32		12.5	4.0	
20	ROLLER PIN	DIA 55	EN8	1		18.6	18.6	
21	R BUSH	DIA 45	MS	0.32		12.5	4.0	
22	ROLLER	DIA 110	EN8	0.18		74.6	13.4	
23	C PIN	DIA 32	EN8	3.64		6.3	23.0	
24	OT BUSH	DIA 55	MS	1.148		18.6	21.4	
25	IN BUSH	DIA 65	MS	1.148		26.0	29.9	
26	CAP WASHER	DIA 75	MS	0.28		34.7	9.7	
27	WASHER	DIA 45	MS	0.168		12.5	2.1	
28	CYL PIN	DIA 40	EN8	2.6		9.9	25.6	
29	wheel	DIA 65	EN8	0.24		26.0	6.2	
30	axle	sq, bar 60 x 60	EN9	3		33.2	99.5	
31								
32								
18	Hydraulic Single acting	Cylinder Bore-63 x Rod 45 x 1400 Stroke working pressure -150bar	ms		2nos			
20	Power pack	3hp, 3Ph, 40ltr tank Capacity Operation - Single acting Cylinder -2nos, operating with hand pump operating	ms		1nos			
21	Control Panel	3hp, 3Ph, IP65			1nos			
22	Tyre wheel	Solid tyre dia500 x 125mm			4nos			
22								
						ACTUL WEIGHT	1585.9	
							158.5891641	
						TOTAL WEIGHT	1744.5	

